



## Wisconsin Department of Transportation

August 6, 2026

### Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #11: 1227-08-73, WISC 2026440**  
**Manitowoc – Green Bay**  
**STH 172 – Atkinson Drive**  
**IH 43**  
**Brown County**

### Letting of August 11, 2026

This is Addendum No. 02, which provides for the following:

#### Schedule of Items:

| Added Bid Item Quantities |                   |      |                                  |                |                               |
|---------------------------|-------------------|------|----------------------------------|----------------|-------------------------------|
| Bid Item                  | Item Description  | Unit | Proposal Total Prior to Addendum | Quantity Added | Proposal Total After Addendum |
| 205.0100                  | Excavation Common | CY   | 0                                | 2,202          | 2,202                         |

#### Plan Sheets:

| Added Plan Sheets |                                                             |
|-------------------|-------------------------------------------------------------|
| Plan Sheet        | Plan Sheet Title (brief description of why sheet was added) |
| 271A              | Added Miscellaneous Quantities – Excavation Common summary  |

#### **Schedule of Items**

Attached, dated August 6, 2026, are the revised Schedule of Items Page 14.

#### **Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Added: 271A

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

EXCAVATION COMMON

| DIVISION            | FROM/TO STATION           | LOCATION            | 205.0100<br>COMMON EXCAVATION<br>(1) |                | SALVAGED/UNUSABLE<br>PAVEMENT MATERIAL<br>(4) | AVAILABLE<br>MATERIAL<br>(5) | UNEXPANDED<br>FILL | EXPANDED FILL<br>(13)<br>FACTOR 1.25 |   | MASS ORDINATE +/-<br>(14) | WASTE | 208.0100<br>BORROW |
|---------------------|---------------------------|---------------------|--------------------------------------|----------------|-----------------------------------------------|------------------------------|--------------------|--------------------------------------|---|---------------------------|-------|--------------------|
|                     |                           |                     | CUT<br>(2)                           | EB5 EXCAVATION |                                               |                              |                    |                                      |   |                           |       |                    |
| DIVISION 1          |                           |                     |                                      |                |                                               |                              |                    |                                      |   |                           |       |                    |
|                     | 3359+66'SB to 3362+83'SB' | IH 43 SB at B-5-198 | 2,202                                | 0              | 889                                           | 1,313                        | 0                  | 0                                    | 0 | 1,313                     | 1,313 | 0                  |
| DIVISION 1 SUBTOTAL |                           |                     | 2,202                                | 0              | 889                                           | 1,313                        | 0                  | 0                                    | 0 | 1,313                     | 1,313 | 0                  |
| GRAND TOTAL         |                           |                     | 2,202                                | 0              | 889                                           | 1,313                        | 0                  | 0                                    | 0 | 1,313                     | 1,313 | 0                  |
| TOTAL COMMON EXC    |                           |                     | 2,202                                | 2,202          |                                               |                              |                    |                                      |   |                           |       |                    |

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
- (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
- (4) SALVAGED/UNUSABLE PAVEMENT MATERIAL
- (5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
- (13) EXPANDED FILL FACTOR = 1.25
- (14) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.

Addendum No. 02  
ID 1227-08-73  
Added Sheet 271A  
August 6, 2026



## Proposal Schedule of Items

Page 14 of 14

Proposal ID: 20260811011 Project(s): 1227-08-73

Federal ID(s): WISC 2026440

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

| Proposal Line Number | Item ID Description                                                             | Approximate Quantity and Units | Unit Price | Bid Amount |
|----------------------|---------------------------------------------------------------------------------|--------------------------------|------------|------------|
| 0382                 | SPV.0060<br>Special 04. Resetting Pipe End                                      | 1.000<br>EACH                  | _____.     | _____.     |
| 0384                 | SPV.0060<br>Special 05. Removing Sand Barrel Arrays with Restoration            | 3.000<br>EACH                  | _____.     | _____.     |
| 0386                 | SPV.0060<br>Special 06. Removing Raised Pavement Markers                        | 161.000<br>EACH                | _____.     | _____.     |
| 0388                 | SPV.0060<br>Special 07. Concrete Control Cabinet Bases Type 9 NE Region Special | 1.000<br>EACH                  | _____.     | _____.     |
| 0390                 | SPV.0090<br>Special 01. Grading, Shaping and Finishing Ditch                    | 1,629.000<br>LF                | _____.     | _____.     |
| 0392                 | SPV.0090<br>Special 02. Concrete Joint and Crack Cleaning and Repair            | 5,670.000<br>LF                | _____.     | _____.     |
| 0394                 | SPV.0090<br>Special 04. Cured in Place Pipe Liner, 60-Inch                      | 275.000<br>LF                  | _____.     | _____.     |
| 0396                 | SPV.0170<br>Special 01. Cable Guard Median Grading and Shaping                  | 122.000<br>STA                 | _____.     | _____.     |
| 0398                 | 205.0100<br>Excavation Common                                                   | 2,202.000<br>CY                | _____.     | _____.     |
| Section: 0001        |                                                                                 |                                | Total:     | _____.     |
|                      |                                                                                 |                                | Total Bid: | _____.     |

