



Wisconsin Department of Transportation

September 10, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631

Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #14: 1140-00-78, WISC 2026421
New London – Clintonville
Church Road to Reinke Road
USH 45
Waupaca County

Letting of September 15, 2026

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
204.0110	Removing Asphaltic Surface	SY	658	31	689
204.0150	Removing Curb & Gutter	LF	627	-283	344
205.0100	Excavation Common	CY	8811	106	8917
465.0105	Asphaltic Surface	TON	2588	246	2834
690.0250	Sawing Concrete	LF	170	292	462

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
204.0100	Removing Concrete Pavement	SY	0	2000	2000
211.0101	Prepare Foundation for Asphaltic Paving (project) 01. 1140-00-78	EACH	0	1	1

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
32	1140-00-78 Question #3 (1 page) – Increase Removing Asphaltic Surface
33	1140-00-78 Question #3 (1 page) – Increase Excavation Common
34-35	1140-00-78 Question #3 (2 pages) – Increase Asphaltic Surface
37	1140-00-78 Question #3 (1 page) – Decrease Removing Curb & Gutter
32	1140-00-78 Question #5 (1 page) – Add Removing Concrete Pavement
41	1140-00-78 Question #5 (1 pages) – Increase Sawing Concrete
34-35	1140-00-78 Question #6 (2 pages) – Add Prepare Foundation for Asphaltic Paving (project) 01. 1140-00-78

Other

Revise the contract completion time from 50 working days to 55 working days (an increase in 5 working days).

Schedule of Items

Attached, dated September 10, 2026, are the revised Schedule of Items 1 – 8.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 32, 33, 34, 35, 37, and 41.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

REMOVALS

203.0100		203.0220		204.0100	
REMOVING SMALL PIPE CULVERTS		REMOVING STRUCTURE (STRUCTURE)		REMOVING CONCRETE PAVEMENT	
ROADWAY	SIDE	STA	EACH	SY	
USH 45	LT/RT	170+53	1	-	240
USH 45	LT/RT	170+64	1	-	-
USH 45	LT/RT	198+33	-	1	-
USH 45	LT/RT	257+68	1	-	-
USH 45	LT/RT	316+40	-	1	220
USH 45	LT/RT	324+62	1	-	220
USH 45	LT/RT	336+24	1	-	220
USH 45	LT/RT	454+16	1	-	220
USH 45	LT/RT	511+63	1	-	220
USH 45	LT/RT	607+85	-	1	-
USH 45	LT/RT	659+05	1	-	220
USH 45	LT/RT	693+55	1	-	220
USH 45	LT/RT	704+94	1	-	220
TOTAL			10	3	2,000

ASPHALTIC SURFACE MILLING

204.0110		204.0115		204.0120		SPV.0180.01	
REMOVING ASPHALTIC SURFACE		REMOVING ASPHALTIC SURFACE BUTT JOINTS		REMOVING ASPHALTIC SURFACE MILLING		REMOVING DISTRESSED ASPHALTIC SURFACE MILLING	
ROADWAY	SIDE	STA	TO	STA	SY	SY	COMMENTS
USH 45	MAINLINE	168+00	-	731+75	48	34	
CRAN RD	LT	188+54	-		6	29	
SASSE RD	RT	188+54	-		-	34	
BECKERT RD	RT	243+63	-		-	32	
HOFFMAN RD	LT	255+05	-		-	29	
BOARDWALK	RT	271+53	-		-	36	
CTH N	LT	295+00	-		4	32	
CTH VW	RT	295+00	-		4	33	
DAVIS RD	LT	322+50	-		-	33	
GIELOW RD	RT	343+41	-		-	17	
POEHLMAN RD	LT	351+30	-		-	30	
BREITING RD	RT	351+30	-		-	30	
FITZGERALD RD	LT	373+24	-		5	32	
ELM TREE RD	RT	400+00	-		-	26	
BLUEBERRY RD	LT	426+47	-		4	33	
BLUEBERRY RD	RT	426+47	-		4	34	
STH 22	LT	479+73	-		-	48	
STH 76	RT	479+73	-		-	49	
ALTERRAIN LN	LT	489+00	-		-	22	
SILVER CREEK RD	LT	522+81	-		-	26	
BEAR CREEK RD	LT	591+79	-		-	26	
BEAR CREEK RD	RT	591+79	-		-	26	
DEER CREEK RD	RT	618+31	-		-	34	
ELMDALE RD	LT	645+00	-		-	26	
WILLOW RD	RT	659+06	-		-	26	
BROADVIEW LN	LT	673+40	-		4	26	
CTH O	LT	703+87	-		-	45	
CTHD	RT	703+87	-		-	34	
REINKE RD	LT	730+68	-		-	42	
REINKE RD	RT	730+68	-		-	42	
USH 45	LT/RT	731+75	-		-	76	
USH 45	LT/RT	168+00	-	731+75	610	-	DRIVEWAYS
USH 45	PROJECT	-	-	UNDISTRIBUTED	-	-	
TOTAL					689	1,042	
					255,030	7,651	

Addendum No. 01
ID 1140-00-78
Revised Sheet 32
September 10, 2026

Addendum No. 01
ID 1140-00-78
Revised Sheet 33
September 10, 2026

DIVISION	FROM/TO STATION	LOCATION	COMMON EXCAVATION (1)		SALVAGED/UNSALVAGED PAVEMENT MATERIAL (4)	AVAILABLE MATERIAL (5)	UNEXPANDED FILL (6)	EXPANDED FILL (13)		MASS ORDINATE +/- (14)	WASTE	208.0100 BORROW	COMMENT
			CUT (2)	EBS EXCAVATION (3)				EXPANDED FILL 1.25	EXPANDED FILL (13)				
USH 45 MAINLINE	171+50 - 180+00	RT	1,041	0	44	997	0	0	0	997	0	0	REDITCHING
PROJECT TOTAL			1,041	0	44	997	0	0	0	997	0	0	

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
(2) SALVAGED/UNSALVAGED PAVEMENT MATERIAL IS INCLUDED IN CUT.
(3) EBS EXCAVATION TO BE BACKFILLED WITH SELECT BORROW MATERIAL. NOTE: THIS IS DESIGNERS CHOICE, CAN BE BACKFILLED WITH BORROW, OR CUT AS WELL.
(4) SALVAGED/UNSALVAGED PAVEMENT MATERIAL
(5) AVAILABLE MATERIAL = CUT - SALVAGED/UNSALVAGED PAVEMENT MATERIAL
(13) EXPANDED FILL FACTOR = 1.25
DEPEND ON SELECTIONS:
OR
OR
OR
(14) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.

EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH - REDUCED EBS) * FILL FACTOR
EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED EBS) * FILL FACTOR
EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH) * FILL FACTOR
EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK) * FILL FACTOR

AGGREGATE ITEMS

		211.0400		305.0110		305.0120		305.0500		624.0100	
		PREPARE FOUNDATION FOR ASPHALTIC SHOULDERS		BASE AGGREGATE DENSE 3/4-INCH		BASE AGGREGATE DENSE 1 1/4-INCH		SHAPING SHOULDERS		WATER	
ROADWAY	STA	TO	STA	TON	TON	TON	TON	STA	MGAL	COMMENTS	
USH 45	168+00	-	170+32	6	30	-	-	6	-	CULVERT PIPE	
USH 45	170+02	-	171+22	-	80	490	-	-	-	CULVERT PIPE	
USH 45	170+32	-	191+00	40	190	-	-	40	-	CULVERT PIPE	
USH 45	191+00	-	265+87	150	670	-	-	150	-	CULVERT PIPE	
USH 45	197+78	-	198+88	-	70	560	-	-	-	CULVERT PIPE	
USH 45	257+13	-	258+23	-	70	560	-	-	-	CULVERT PIPE	
USH 45	265+87	-	386+92	242	1080	-	-	242	-	CULVERT PIPE	
USH 45	315+85	-	316+95	-	70	490	-	-	-	CULVERT PIPE	
USH 45	324+07	-	325+17	-	70	420	-	-	-	CULVERT PIPE	
USH 45	335+69	-	336+79	-	70	420	-	-	-	CULVERT PIPE	
USH 45	386+92	-	468+36	164	750	-	-	164	-	CULVERT PIPE	
USH 45	453+61	-	454+71	-	70	560	-	-	-	CULVERT PIPE	
USH 45	491+54	-	495+47	10	40	-	-	10	-	CULVERT PIPE	
USH 45	495+47	-	539+00	86	390	-	-	86	-	CULVERT PIPE	
USH 45	511+08	-	512+18	-	70	420	-	-	-	CULVERT PIPE	
USH 45	539+00	-	550+20	24	110	-	-	24	-	CULVERT PIPE	
USH 45	550+20	-	641+94	182	820	-	-	182	-	CULVERT PIPE	
USH 45	607+30	-	608+40	-	70	420	-	-	-	CULVERT PIPE	
USH 45	641+94	-	653+90	24	110	-	-	24	-	CULVERT PIPE	
USH 45	658+50	-	659+60	-	70	910	-	-	-	CULVERT PIPE	
USH 45	693+00	-	694+10	-	70	670	-	-	-	CULVERT PIPE	
USH 45	704+39	-	705+49	-	70	790	-	-	-	CULVERT PIPE	
USH 45	653+90	-	720+82	134	600	-	-	134	-	CULVERT PIPE	
PROJECT	168+00	-	731+35	-	-	-	-	-	-	250	
TOTAL				1,062	5,640	6,710	1,062	250			

EXCAVATION COMMON

		205.0100	
		EXCAVATION COMMON	
ROADWAY SIDE	STA	CY	COMMENTS
USH 45	170+53	510	CULVERT PIPE
USH 45	198+33	710	CULVERT PIPE
USH 45	257+68	650	CULVERT PIPE
USH 45	316+40	470	CULVERT PIPE
USH 45	324+62	470	CULVERT PIPE
USH 45	336+24	470	CULVERT PIPE
USH 45	454+16	620	CULVERT PIPE
USH 45	511+03	550	CULVERT PIPE
USH 45	607+85	510	CULVERT PIPE
USH 45	659+05	1020	CULVERT PIPE
USH 45	693+55	830	CULVERT PIPE
USH 45	704+94	960	CULVERT PIPE
USH 45	PROJECT	106	SIDEROAD CULVERTS
TOTAL		7,876	

ASPHALT ITEMS (1 OF 2)

ROADWAY	SIDE	STA	TO	STA	211.0101.01 PREPARE FOUNDATION FOR ASPHALTIC PAVING (PROJECT) (01.1140- 00-78)	455.0605 TACK COAT	460.6224 HMA PAVEMENT 4 MT 58-28 S	465.0105 ASPHALTIC SURFACE	465.0110 ASPHALTIC SURFACE PATCHING	465.0120 ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES	465.0315 ASPHALTIC FLUMES	465.0520 ASPHALTIC RUMBLE STRIPS, SHOULDER	465.0560 ASPHALTIC RUMBLE STRIPS, CENTERLINE	LF	LF	COMMENTS
USH 45	MAINLINE	168+00	-	731+75	1	37,500	52,490	-	-	-	-	85,610	47,810	-	-	PROJECT
USH 45	L/RT	170+53	-		30	30	-	170	-	-	-	-	-	-	-	CULVERT PIPE
USH 45	LT	188+54	-		30	30	40	-	-	-	-	-	-	-	-	CRAN RD
USH 45	RT	188+54	-		30	30	40	-	-	-	5	-	-	-	-	SASSE RD
USH 45	L/RT	198+33	-		40	40	-	210	-	-	-	-	-	-	-	CULVERT PIPE
USH 45	RT	243+63	-		30	30	40	-	-	-	-	-	-	-	-	BECKERT RD
USH 45	LT	255+05	-		30	30	40	-	-	-	-	-	-	-	-	HOFFMAN RD
USH 45	L/RT	257+68	-		40	40	-	210	-	-	-	-	-	-	-	CULVERT PIPE
USH 45	RT	271+53	-		30	30	40	-	-	-	-	-	-	-	-	BOARDWALK COMM.
USH 45	LT	295+00	-		30	30	30	17	-	-	-	-	-	-	-	CTH N
USH 45	RT	295+00	-		30	30	40	17	-	-	-	-	-	-	-	CTH WW
USH 45	L/RT	316+40	-		40	40	-	180	-	-	-	-	-	-	-	CULVERT PIPE
USH 45	LT	322+50	-		50	50	70	-	-	-	-	-	-	-	-	DAMS RD
USH 45	L/RT	324+62	-		30	30	-	150	30	-	-	-	-	-	-	CULVERT PIPE
USH 45	L/RT	336+24	-		30	30	-	150	-	-	-	-	-	-	-	CULVERT PIPE
USH 45	RT	343+41	-		10	10	-	-	-	-	-	-	-	-	-	GIELOW RD
USH 45	LT	351+30	-		30	30	40	-	-	-	-	-	-	-	-	POEHLMAN RD
USH 45	RT	351+30	-		30	30	40	-	-	-	-	-	-	-	-	BREITING RD
USH 45	LT	373+24	-		30	30	40	15	-	-	-	-	-	-	-	FITZGERALD RD
USH 45	RT	400+00	-		30	30	40	-	-	-	-	-	-	-	-	ELM TREE RD
USH 45	RT	400+20	-		-	-	12	-	-	-	5	-	-	-	-	ELM TREE RD
USH 45	LT	426+47	-		30	30	40	19	-	-	-	-	-	-	-	BLUEBERRY RD
USH 45	RT	426+47	-		30	30	40	30	-	-	-	-	-	-	-	BLUEBERRY RD
USH 45	L/RT	426+54	-	426+96	-	-	-	-	-	-	9	-	-	-	-	BLUEBERRY RD
USH 45	L/RT	454+16	-		40	40	-	210	-	-	-	-	-	-	-	CULVERT PIPE
SUBTOTAL					1	38,200	53,080	1,390	--	--	19	85,610	47,810			

Addendum No. 01
ID 1140-00-78
Revised Sheet 34
September 10, 2026

ASPHALT ITEMS (2 OF 2)

ROADWAY	SIDE	STA	TO	STA	EACH	GAL	TON	TON	TON	TON	SY	LF	LF	COMMENTS	211.0101.01 PREPARE FOUNDATION FOR ASPHALTIC PAVING (PROJECT) (01, 1140- 00-78)	455.0605	460.0224	485.0105	485.0110	485.0120	485.0315	485.0520	485.0560
USH 45	L/RT	479+36	-	-	-	-	-	-	-	-	9	-	-	STH 76/STH 22									
USH 45	LT	489+00	-	-	-	10	10	-	-	-	-	-	-	ALTERRAIN LN									
USH 45	L/RT	511+63	-	-	-	30	-	150	-	-	-	-	-	CULVERT PIPE									
USH 45	LT	522+81	-	-	-	30	40	28	-	-	-	-	-	SILVER CREEK RD									
USH 45	LT	591+79	-	-	-	30	40	18	-	-	-	-	-	BEAR CREEK RD									
USH 45	RT	591+79	-	-	-	30	40	26	-	-	-	-	-	BEAR CREEK RD									
USH 45	L/RT	607+85	-	-	-	30	-	150	-	-	-	-	-	CULVERT PIPE									
USH 45	RT	616+31	-	-	-	30	40	-	-	-	-	-	-	DEER CREEK RD									
USH 45	LT	654+00	-	-	-	40	50	17	-	-	-	-	-	ELMDALE RD									
USH 45	L/RT	659+05	-	-	-	80	-	410	-	-	-	-	-	CULVERT PIPE									
USH 45	RT	659+06	-	-	-	30	40	13	-	-	-	-	-	WILLOW RD									
USH 45	LT	673+40	-	-	-	30	40	23	-	-	-	-	-	BROADVIEW LN									
USH 45	L/RT	693+55	-	-	-	50	-	260	-	-	-	-	-	CULVERT PIPE									
USH 45	LT	703+87	-	-	-	30	40	-	-	-	-	-	-	CTH O									
USH 45	RT	703+87	-	-	-	30	40	-	-	-	-	-	-	CTH D									
USH 45	L/RT	704+94	-	-	-	60	-	320	-	-	-	-	-	CULVERT PIPE									
USH 45	LT	730+68	-	-	-	30	30	-	-	-	-	-	-	REINKE RD									
USH 45	RT	730+68	-	-	-	20	30	-	-	-	-	-	-	REINKE RD									
USH 45	L/RT	168+00	-	731+75	-	540	-	-	860	-	-	-	-	REMOVING DISTRESSED ASPHALTIC SURFACE MILLING									
USH 45	L/RT	168+00	-	731+75	-	-	-	-	-	50	-	-	-	DRIVEWAYS									
USH 45	L/RT	168+00	-	731+75	-	-	-	29	-	-	-	-	-	CURB & GUTTER									
SUBTOTAL						1,130	440	1,444	860	50	9	-	-										
TOTAL						1	39,330	53,520	2,834	860	50	28	85,610	47,810									

Addendum No. 01
ID 1140-00-78
Revised Sheet 35
September 10, 2026

Addendum No. 01
ID 1140-00-78
Revised Sheet 41
September 10, 2026

CONSTRUCTION STAKING

850.5500		850.6000		850.8000		650.9920	
CONSTRUCTION STAKING CURB AND GUTTER		CONSTRUCTION STAKING PIPE CULVERTS		CONSTRUCTION STAKING RESURFACING REFERENCE		CONSTRUCTION STAKING SLOPE STAKES	
ROADWAY	STATION TO	STATION	LF	EACH	LF	LF	LF
USH 45	170+53	-	-	1	-	200	-
USH 45	170+64	-	-	1	-	200	-
USH 45	171+12	180+37	-	-	-	925	-
USH 45	198+33	-	-	1	-	200	-
USH 45	257+68	-	-	1	-	200	-
USH 45	316+40	-	-	1	-	200	-
USH 45	324+62	-	-	1	-	200	-
USH 45	336+24	-	-	1	-	200	-
USH 45	454+16	-	-	1	-	200	-
USH 45	511+63	-	-	1	-	200	-
USH 45	607+85	-	-	1	-	200	-
USH 45	659+05	-	-	1	-	200	-
USH 45	693+55	-	-	1	-	200	-
USH 45	704+94	-	-	1	-	200	-
USH 45	168+00	731+75	-	-	56,375	-	-
USH 45	187+75	674+25	627	-	-	-	-
TOTAL			627	13	56,375	3,525	

SAWING

690.0150		690.0250	
SAWING ASPHALT		SAWING CONCRETE	
ROADWAY	STATION TO	STATION	LF
USH 45	170+03	171+14	63
USH 45	197+83	198+83	84
USH 45	257+18	258+18	123
USH 45	315+90	316+90	74
USH 45	324+12	325+12	64
USH 45	335+74	336+74	60
USH 45	453+66	454+66	84
USH 45	511+13	512+13	60
USH 45	607+35	608+35	60
USH 45	658+55	659+55	139
USH 45	693+05	694+05	108
USH 45	704+44	705+44	148
USH 45	168+00	731+75	222
USH 45	168+00	731+75	2710
TOTAL			3999

PUBLIC LAND REFERENCE MONUMENTS

680.0100

PUBLIC LAND REFERENCE MONUMENT VERIFY AND RESET					
ROADWAY	SECTION	STATION	OFFSET	TOWNSHIP	RANGE
USH 45	1	351+29	-0.8 LT	T23N	R14E
USH 45	36	373+32	-0.24 LT	T24N	R14E
USH 45	36	399+96	-0.39 LT	T24N	R14E
USH 45	25	426+51	0'	T24N	R14E
USH 45	25	453+02	-5.05 LT	T24N	R14E
USH 45	24	476+72	-1.35 LT	T24N	R14E
USH 45	11	591+80	5.55 RT	T24N	R14E
USH 45	11	618+33	-5.18 LT	T24N	R14E
USH 45	2	644+78	32.65 RT	T24N	R14E
TOTAL					9

PROJECT NO: 1140-00-78

HWY: USH 45

COUNTY: WAUPACA

MISCELLANEOUS QUANTITIES

SHEET

41

E

FILE NAME: C:\USERS\FREDERICK\ONE DRIVE - DAAR CORPORATION\DOCUMENTS - NC DESIGN\1140-00-08_USH 45 NORTH_WAUPACA COUNTY\CD11400008\08SHEETSP\PLAN\030201.MXD DWG PLOT DATE: 9/7/2026 8:42 PM PLOT BY: FREDERICK KOTH PLOT NAME: 1"=1' WSDOT/CADD/S-SHEET 42



Proposal Schedule of Items

Page 1 of 8

Proposal ID: 20260915014 Project(s): 1140-00-78

Federal ID(s): WISC 2026421

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	10.000 EACH	_____.	_____.
0004	203.0220 Removing Structure (structure) 01. STA. 198+33	1.000 EACH	_____.	_____.
0006	203.0220 Removing Structure (structure) 02. STA. 316+40	1.000 EACH	_____.	_____.
0008	203.0220 Removing Structure (structure) 03. STA. 607+85	1.000 EACH	_____.	_____.
0010	204.0110 Removing Asphaltic Surface	689.000 SY	_____.	_____.
0012	204.0115 Removing Asphaltic Surface Butt Joints	1,042.000 SY	_____.	_____.
0014	204.0120 Removing Asphaltic Surface Milling	255,030.000 SY	_____.	_____.
0016	204.0150 Removing Curb & Gutter	344.000 LF	_____.	_____.
0018	205.0100 Excavation Common	8,917.000 CY	_____.	_____.
0020	208.1500.S Temporary Lane Shift During Culvert Work	13.000 EACH	_____.	_____.
0022	211.0400 Prepare Foundation for Asphaltic Shoulders	1,062.000 STA	_____.	_____.
0024	213.0100 Finishing Roadway (project) 01. 1140-00-78	1.000 EACH	_____.	_____.
0026	305.0110 Base Aggregate Dense 3/4-Inch	5,640.000 TON	_____.	_____.
0028	305.0120 Base Aggregate Dense 1 1/4-Inch	6,710.000 TON	_____.	_____.



Proposal Schedule of Items

Page 2 of 8

Proposal ID: 20260915014 Project(s): 1140-00-78

Federal ID(s): WISC 2026421

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0030	305.0500 Shaping Shoulders	1,062.000 STA	_____.	_____.
0032	455.0605 Tack Coat	39,330.000 GAL	_____.	_____.
0034	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	1.000 EACH	_____.	_____.
0036	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	2.000 EACH	_____.	_____.
0038	460.2005 Incentive Density PWL HMA Pavement	31,790.000 DOL	1.00000	31,790.00
0040	460.2007 Incentive Density HMA Pavement Longitudinal Joints	11,280.000 DOL	1.00000	11,280.00
0042	460.2010 Incentive Air Voids HMA Pavement	53,520.000 DOL	1.00000	53,520.00
0044	460.6224 HMA Pavement 4 MT 58-28 S	53,520.000 TON	_____.	_____.
0046	465.0105 Asphaltic Surface	2,834.000 TON	_____.	_____.
0048	465.0110 Asphaltic Surface Patching	860.000 TON	_____.	_____.
0050	465.0120 Asphaltic Surface Driveways and Field Entrances	50.000 TON	_____.	_____.
0052	465.0315 Asphaltic Flumes	28.000 SY	_____.	_____.
0054	465.0520 Asphaltic Rumble Strips, Shoulder	85,610.000 LF	_____.	_____.
0056	465.0560 Asphaltic Rumble Strips, Centerline	47,810.000 LF	_____.	_____.
0058	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	80.000 LF	_____.	_____.



Proposal Schedule of Items

Page 3 of 8

Proposal ID: 20260915014 Project(s): 1140-00-78

Federal ID(s): WISC 2026421

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0060	522.0430 Culvert Pipe Reinforced Concrete Class IV 30-Inch	56.000 LF	_____.	_____.
0062	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	2.000 EACH	_____.	_____.
0064	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	2.000 EACH	_____.	_____.
0066	522.2424 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 24x38-Inch	96.000 LF	_____.	_____.
0068	522.2429 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 29x45-Inch	72.000 LF	_____.	_____.
0070	522.2434 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 34x53-Inch	256.000 LF	_____.	_____.
0072	522.2624 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 24x38-Inch	4.000 EACH	_____.	_____.
0074	522.2629 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 29x45-Inch	2.000 EACH	_____.	_____.
0076	522.2634 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 34x53-Inch	8.000 EACH	_____.	_____.
0078	522.2638 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 38x60-Inch	4.000 EACH	_____.	_____.
0080	522.2643 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 43x68-Inch	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 4 of 8

Proposal ID: 20260915014 Project(s): 1140-00-78

Federal ID(s): WISC 2026421

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0082	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	627.000 LF	_____.	_____.
0084	606.0200 Riprap Medium	15.000 CY	_____.	_____.
0086	611.8115 Adjusting Inlet Covers	21.000 EACH	_____.	_____.
0088	618.0100 Maintenance and Repair of Haul Roads (project) 01. 1140-00-78	1.000 EACH	_____.	_____.
0090	619.1000 Mobilization	1.000 EACH	_____.	_____.
0092	624.0100 Water	250.000 MGAL	_____.	_____.
0094	625.0100 Topsoil	5,386.000 SY	_____.	_____.
0096	628.1504 Silt Fence	5,514.000 LF	_____.	_____.
0098	628.1520 Silt Fence Maintenance	5,514.000 LF	_____.	_____.
0100	628.1905 Mobilizations Erosion Control	5.000 EACH	_____.	_____.
0102	628.1910 Mobilizations Emergency Erosion Control	5.000 EACH	_____.	_____.
0104	628.2004 Erosion Mat Class I Type B	420.000 SY	_____.	_____.
0106	628.2008 Erosion Mat Urban Class I Type B	4,926.000 SY	_____.	_____.
0108	628.7504 Temporary Ditch Checks	40.000 LF	_____.	_____.
0110	628.7555 Culvert Pipe Checks	78.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 5 of 8

Proposal ID: 20260915014 Project(s): 1140-00-78

Federal ID(s): WISC 2026421

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0112	628.7570 Rock Bags	150.000 EACH	_____.	_____.
0114	629.0210 Fertilizer Type B	4.900 CWT	_____.	_____.
0116	630.0130 Seeding Mixture No. 30	111.000 LB	_____.	_____.
0118	630.0500 Seed Water	54.500 MGAL	_____.	_____.
0120	633.5200 Markers Culvert End	26.000 EACH	_____.	_____.
0122	638.2102 Moving Signs Type II	13.000 EACH	_____.	_____.
0124	638.4000 Moving Small Sign Supports	13.000 EACH	_____.	_____.
0126	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0128	643.0300 Traffic Control Drums	1,720.000 DAY	_____.	_____.
0130	643.0420 Traffic Control Barricades Type III	100.000 DAY	_____.	_____.
0132	643.0705 Traffic Control Warning Lights Type A	200.000 DAY	_____.	_____.
0134	643.0715 Traffic Control Warning Lights Type C	140.000 DAY	_____.	_____.
0136	643.0810 Traffic Control Connected Arrow Boards	10.000 DAY	_____.	_____.
0138	643.0900 Traffic Control Signs	3,670.000 DAY	_____.	_____.
0140	643.1000 Traffic Control Signs Fixed Message	36.000 SF	_____.	_____.
0142	643.1220 Traffic Control Connected Work Zone Start and End Location Markers	10.000 DAY	_____.	_____.



Proposal Schedule of Items

Page 6 of 8

Proposal ID: 20260915014 Project(s): 1140-00-78

Federal ID(s): WISC 2026421

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0144	643.3165 Temporary Marking Line Paint 6-Inch	128,802.000 LF	_____.	_____.
0146	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0148	645.0120 Geotextile Type HR	26.000 SY	_____.	_____.
0150	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	192,980.000 LF	_____.	_____.
0152	646.4040 Marking Line Grooved Wet Ref Epoxy 10-Inch	2,330.000 LF	_____.	_____.
0154	646.5020 Marking Arrow Epoxy	16.000 EACH	_____.	_____.
0156	646.5120 Marking Word Epoxy	14.000 EACH	_____.	_____.
0158	646.6120 Marking Stop Line Epoxy 18-Inch	114.000 LF	_____.	_____.
0160	646.7120 Marking Diagonal Epoxy 12-Inch	185.000 LF	_____.	_____.
0162	646.8120 Marking Curb Epoxy	483.000 LF	_____.	_____.
0164	646.8220 Marking Island Nose Epoxy	17.000 EACH	_____.	_____.
0166	648.0100 Locating No-Passing Zones	10.680 MI	_____.	_____.
0168	650.5500 Construction Staking Curb Gutter and Curb & Gutter	627.000 LF	_____.	_____.
0170	650.6000 Construction Staking Pipe Culverts	13.000 EACH	_____.	_____.
0172	650.8000 Construction Staking Resurfacing Reference	56,375.000 LF	_____.	_____.



Proposal Schedule of Items

Page 7 of 8

Proposal ID: 20260915014 Project(s): 1140-00-78

Federal ID(s): WISC 2026421

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0174	650.9911 Construction Staking Supplemental Control (project) 01. 1140-00-78	1.000 EACH	_____.	_____.
0176	650.9920 Construction Staking Slope Stakes	3,525.000 LF	_____.	_____.
0178	680.0100 Public Land Survey Monument Verify and Reset	9.000 EACH	_____.	_____.
0180	690.0150 Sawing Asphalt	3,999.000 LF	_____.	_____.
0182	690.0250 Sawing Concrete	462.000 LF	_____.	_____.
0184	740.0440 Incentive IRI Ride	44,000.000 DOL	1.00000	44,000.00
0186	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,400.000 HRS	5.00000	12,000.00
0188	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	2,760.000 HRS	5.00000	13,800.00
0190	SPV.0090 Special 01.Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 38X60-Inch	160.000 LF	_____.	_____.
0192	SPV.0090 Special 02.Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 43X68-Inch	184.000 LF	_____.	_____.
0194	SPV.0180 Special 01. Removing Distressed Asphaltic Surface Milling	7,651.000 SY	_____.	_____.
0196	204.0100 Removing Concrete Pavement	2,000.000 SY	_____.	_____.
0198	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 1140-00-78	1.000 EACH	_____.	_____.
Section: 0001			Total:	_____.



Proposal Schedule of Items

Page 8 of 8

Proposal ID: 20260915014 Project(s): 1140-00-78

Federal ID(s): WISC 2026421

Total Bid: _____.