



Wisconsin Department of Transportation

October 1, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #07: 2568-00-71, WISC 2027005
C Milwaukee, N Dr Mlk Jr Dr
Intersections W Center to W Wright
LOC STR
Milwaukee County

2568-00-72, WISC 2027006
C Milwaukee, N Dr Mlk Jr Dr
Intersection With North Ave
LOC STR
Milwaukee County

Letting of October 13, 2026

This is Addendum No. 01, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
96	Pedestal Bases Black, Item SPV.0060.250
97	Poles Type 10-Special Black, Item SPV.0060.251
98	Traffic Signal Standards Aluminum 3.5-FT Black, Item SPV.0060.252
99	Monotube Arms 35-FT-Special Black, Item SPV.0060.253
100	Traffic Signal Face 3S 12-Inch Black, Item SPV.0060.254
101	Traffic Signal Face 4S 12-Inch Black, Item SPV.0060.255
102	Pedestrian Signal Face 12-Inch Black, Item SPV.0060.256
103	Pedestrian Countdown Signal Face 12-Inch Black, Item SPV.0060.257
104	Traffic Signal Mounting Hardware Black (Location) MLK & North, Item SPV.0060.258

Deleted Special Provisions	
Article No.	Description
14	Notice to Contractor – Monotube Stickers

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
657.0100	Pedestal Bases	EA	11	-2	9
657.0352	Poles Type 10-Special	EA	10	-4	6

657.0405	Traffic Signal Standards Aluminum 3.5-FT	EA	7	-2	5
657.0536	Monotube Arms 35-FT-Special	EA	10	-4	6
658.0173	Traffic Signal Face 3S 12-Inch	EA	66	-18	48
658.0412	Pedestrian Signal Face 12-Inch	EA	32	-8	24
SPV.0060.267	Pedestrian Countdown Signal Face 12-Inch	EA	32	-8	24

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
SPV.0060.250	Pedestal Bases Black	EA	0	2	2
SPV.0060.251	Poles Type 10-Special Black	EA	0	4	4
SPV.0060.252	Traffic Signal Standards Aluminum 3.5-FT Black	EA	0	2	2
SPV.0060.253	Monotube Arms 35-FT-Special Black	EA	0	4	4
SPV.0060.254	Traffic Signal Face 3S 12-Inch Black	EA	0	18	18
SPV.0060.255	Traffic Signal Face 4S 12-Inch Black	EA	0	2	2
SPV.0060.256	Pedestrian Signal Face 12-Inch Black	EA	0	8	8
SPV.0060.257	Pedestrian Countdown Signal Face 12-Inch Black	EA	0	8	8
SPV.0060.258	Traffic Signal Mounting Hardware Black (Location) MLK & North	EA	0	1	1

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
658.0174	Traffic Signal Face 4S 12-Inch	EA	2	-2	0
658.5070	Traffic Signal Mounting Hardware (Location) 04. MLK & North	EA	1	-1	0

Plan Sheets:

Revised Plan Sheets – ID 2568-00-72	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
77	Revised Miscellaneous Quantities for Traffic Signals
78	Revised Miscellaneous Quantities for Traffic Signals

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

2568-00-72

October 1, 2026

Special Provisions

14. Deleted

96. Pedestal Bases Black, Item SPV.0060.250

A Description

This special provision describes furnishing and installing black finished pedestal base.

B Materials

Furnish pedestal bases conforming to standard spec 657.2.6. Provide each item with a black exterior finish that is factory applied and powder-coated. Ensure the finish is uniform and free from visible defects, including cracks, chips, peeling, and exposed substrate.

C Construction

Install Pedestal bases Black according to standard specs 657.3.1 and 657.3.5. Handle, transport, and install the pedestal bases in a manner that prevents damage to the factory-applied powder-coated finish. Repair minor finish damage using a manufacturer-recommended coating system that matches the original finish and is approved by the engineer. Replace items with finish damage that the engineer determines cannot be satisfactorily repaired.

D Measurement

The department will measure Pedestal Bases Black by each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.250	Pedestal Bases Black	EACH

Payment for Pedestal Bases Black is full compensation for providing the black, factory-applied, powder-coated exterior finish base including grounding lugs and related mounting hardware for leveling shims; and for corrosion prevention.

97. Poles Type 10-Special Black, Item SPV.0060.251

A Description

This special provision describes furnishing and installing black finished Poles Type 10-Special.

B Materials

Furnish Poles Type 10-Special conforming to standard specs 657.2.1.1 and 657.2.1.2. Provide each item with a black exterior finish that is factory applied and powder-coated. Ensure the finish is uniform and free from visible defects, including cracks, chips, peeling, and exposed substrate.

C Construction

Install Poles Type 10-Special Black according to standard specs 657.3.1 and 657.3.2. Handle, transport, and install the poles in a manner that prevents damage to the factory-applied powder-coated finish. Repair

minor finish damage using a manufacturer-recommended coating system that matches the original finish and is approved by the engineer. Replace items with finish damage that the engineer determines cannot be satisfactorily repaired.

D Measurement

The department will measure Poles Type 10-Special Black by each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.251	Poles Type 10-Special Black	EACH

Payment for Poles Type 10 Special Black is full compensation for providing the black factory-applied, powder-coated exterior finished poles including grounding lugs and related mounting hardware; for hardware and fitting necessary to install the pole; for leveling shims and for corrosion prevention.

98. Traffic Signal Standards Aluminum 3.5-FT Black, Item SPV.0060.252

A Description

This special provision describes furnishing and installing black finished Traffic Signal Standards Aluminum 3.5-FT.

B Materials

Furnish Traffic Signal Standards Aluminum 3.5-FT conforming to standard spec 657.2.5. Provide each item with a black exterior finish that is factory applied and powder-coated. Ensure the finish is uniform and free from visible defects, including cracks, chips, peeling, and exposed substrate.

C Construction

Install Traffic Signal Standards Aluminum 3.5-FT Black according to standard specs 657.3.1 and 657.3.4. Handle, transport, and install the traffic signal standards in a manner that prevents damage to the factory-applied powder-coated finish. Repair minor finish damage using a manufacturer-recommended coating system that matches the original finish and is approved by the engineer. Replace items with finish damage that the engineer determines cannot be satisfactorily repaired.

D Measurement

The department will measure Traffic Signal Standards Aluminum 3.5-FT Black by each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.252	Traffic Signal Standards Aluminum 3.5-FT Black	EACH

Payment for Traffic Signal Standards Aluminum 3.5-FT Black is full compensation for providing the black, factory-applied, powder-coated exterior finish standards including all related mounting hardware.

99. Monotube Arms 35-FT-Special Black, Item SPV.0060.253

A Description

This special provision describes furnishing and installing black finished Monotube Arms 35-FT-Special.

B Materials

Furnish Monotube Arms 35-FT-Special conforming to standard spec 657.2.2. Provide each item with a black exterior finish that is factory applied and powder-coated. Ensure the finish is uniform and free from visible defects, including cracks, chips, peeling, and exposed substrate.

C Construction

Install Monotube Arms 35-FT-Special Black according to standard specs 657.3.1 and 657.3.3. Handle, transport, and install the monotube arms in a manner that prevents damage to the factory-applied powder-coated finish. Repair minor finish damage using a manufacturer-recommended coating system that matches the original finish and is approved by the engineer. Replace items with finish damage that the engineer determines cannot be satisfactorily repaired.

D Measurement

The department will measure Monotube Arms 35-FT-Special Black as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.253	Monotube Arms 35-FT-Special Black	EACH

Payment for Monotube Arms 35-FT-Special Black is full compensation for providing the black, factory-applied, powder-coated exterior finish arms; for high-strength bolt, nut, washer assemblies and DTIs including those required for testing; and for providing related mounting hardware, level shims.

100. Traffic Signal Face 3S 12-Inch Black, SPV.0060.254.

A Description

This special provision describes furnishing and installing black finished Traffic Signal Face 3S 12-inch.

B Materials

Furnish traffic signal faces conforming to standard spec 658.2, including the signal housing, visor, LED modules, and backplate. Provide the signal housing, visor, and backplate with a black exterior finish that is factory applied and powder-coated. Ensure the finish is uniform and free from visible defects, including cracks, chips, peeling, and exposed substrate.

C Construction

Install Traffic Signal Face 3S 12-Inch Black as shown in plans and in accordance to standard spec 658.3. Handle, transport, and install the traffic signal faces in a manner that prevents damage to the factory-applied powder-coated finish. Repair minor finish damage using a manufacturer-recommended coating system that matches the original finish and is approved by the engineer. Replace traffic signal faces with finish damage that the engineer determines cannot be satisfactorily repaired.

D Measurement

The department will measure Traffic Signal Face 3S 12-Inch Black by each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.254	Traffic Signal Face 3S 12-Inch Black	EACH

Payment for Traffic Signal Face 3S 12-Inch Black is full compensation for providing a complete and functioning assembly.

101. Traffic Signal Face 4S 12-Inch Black, SPV.0060.255.

A Description

This special provision describes furnishing and installing black finished Traffic Signal Face 4S 12-inch.

B Materials

Furnish traffic signal faces conforming to standard spec 658.2, including the signal housing, visor, LED modules, and backplate. Provide the signal housing, visor, and backplate with a black exterior finish that is factory applied and powder-coated. Ensure the finish is uniform and free from visible defects, including cracks, chips, peeling, and exposed substrate.

C Construction

Install Traffic Signal Face 4S 12-Inch Black as shown in plans and in accordance to standard spec 658.3. Handle, transport, and install the traffic signal faces in a manner that prevents damage to the factory-applied powder-coated finish. Repair minor finish damage using a manufacturer-recommended coating system that matches the original finish and is approved by the engineer. Replace traffic signal faces with finish damage that the engineer determines cannot be satisfactorily repaired.

D Measurement

The department will measure Traffic Signal Face 4S 12-Inch Black by each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.255	Traffic Signal Face 4S 12-Inch Black	EACH

Payment for Traffic Signal Face 4S 12-Inch Black is full compensation for providing a complete and functioning assembly.

102. Pedestrian Signal Face 12-Inch Black, SPV.0060.256.

A Description

This special provision describes furnishing and installing black finished Pedestrian Signal Face 12-inch.

B Materials

Furnish traffic signal faces conforming to standard spec 658.2, including the signal housing, visor, and LED modules. Provide the signal housing, and visor with a black exterior finish that is factory applied and powder-coated. Ensure the finish is uniform and free from visible defects, including cracks, chips, peeling, and exposed substrate.

C Construction

Install Pedestrian Signal Face 12-Inch Black as shown in plans and in accordance to standard spec 658.3. Handle, transport, and install the traffic signal faces in a manner that prevents damage to the factory-applied powder-coated finish. Repair minor finish damage using a manufacturer-recommended coating system that matches the original finish and is approved by the engineer. Replace traffic signal faces with finish damage that the engineer determines cannot be satisfactorily repaired.

D Measurement

The department will measure Traffic Signal Face 3S 12-Inch Black by each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.256	Pedestrian Signal Face 12-Inch Black	EACH

Payment for Pedestrian Signal Face 12-Inch Black is full compensation for providing a complete and functioning assembly.

103. Pedestrian Countdown Signal Face 12-Inch Black, SPV.0060.257.

A Description

This special provision describes furnishing and installing black finished Pedestrian Countdown Signal Face 12-inch in accordance to the following standards.

B Materials

Furnish a 12-Inch Light Emitting Diode (LED) Pedestrian Countdown Module that meets ITE PTCSI-STD Part 2 from March 2004 or current Institute of Transportation Engineer (ITE) standards. The countdown digits shall be displayed with an LED color/type of Portland Orange. The unit shall be able to operate when exposed to temperatures between -40 to 165 degrees Fahrenheit. The operating voltage shall be between 80 to 135VAC, and the wattage drawn shall be 7W.

C Construction

Install Pedestrian Signal Face 12-Inch Black as shown in plans and in accordance to standard spec 658.3. The Pedestrian Countdown Signal Face 12-Inch shall be installed in the same housing and immediately below the Pedestrian Signal Face 12-Inch.

D Measurement

The department will measure Pedestrian Countdown Signal Face 12-Inch Black by each unit, acceptably completed.

E Basis of Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.257	Pedestrian Countdown Signal Face 12-Inch Black	EACH

Payment for Pedestrian Countdown Signal Face 12-Inch Black is full compensation for providing a complete and functioning assembly.

104. Traffic Signal Mounting Hardware Black (Location) MLK & North, SPV.0060.258.

A Description

This special provision describes furnishing and installing black finished Traffic Signal Mounting Hardware.

B Materials

Furnish signal mounting hardware conforming to standard spec 658.2. Provide each item with a black exterior finish that is factory applied and powder-coated. Ensure the finish is uniform and free from visible defects, including cracks, chips, peeling, and exposed substrate.

C Construction

Install Signal Mounting Hardware Black according to standard spec 658.3. Handle, transport, and install the signal mounting hardware in a manner that prevents damage to the factory-applied powder-coated finish. Repair minor finish damage using a manufacturer-recommended coating system that matches the original finish and is approved by the engineer. Replace items with finish damage that the engineer determines cannot be satisfactorily repaired.

D Measurement

The department will measure Signal Mounting Hardware Black (Location) MLK & North by each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.258	Traffic Signal Mounting Hardware Black (Location) MLK & North	EACH

Payment for Signal Mounting Hardware Black is full compensation for providing the black, factory-applied, powder-coated exterior finish hardware, including spacers.

Schedule of Items

Attached, dated October 1, 2026, are the revised Schedule of Items Pages 1 – 14.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
2568-00-72 Revised: 77, 78.

END OF ADDENDUM

ALL ITEMS IN THIS SHEET ARE CATEGORY 0010

TRAFFIC SIGNALS QUANTITIES - N MLK JR DR & W NORTH AVE

TRAFFIC SIGNALS REMOVALS

204.0195*		653.0905*	
LOCATION	LOCATION	REMOVING CONCRETE BASES	REMOVING PULL BOXES
NUMBER		EACH	EACH
XBA	14+29', 60' L	-	1
XBB	14+29', 57' L	-	1
XBC	14+33', 41' R	-	1
XBD	14+31', 47' R	-	1
XBE	14+31', 47' R	-	1
XBF	13+67', 49' R	1	-
XBG	13+67', 56' L	-	1
XBH	13+67', 60' L	-	1
TOTAL		1	7

TRAFFIC SIGNALS REMOVALS

659.5000.S*	
LOCATION	LAMP, BALLAST, LED, SWITCH DISPOSAL BY CONTRACTOR
	EACH
PEDESTRIAL SIGNAL	8
TRAFFIC SIGNAL 3-SECTION	12
TOTAL	20

TEMPORARY TRAFFIC SIGNALS

661.0201.04	
TEMPORARY TRAFFIC SIGNALS FOR INTERSECTIONS MLK & NORTH	
LOCATION	EACH
MLK AT NORTH	1
TOTAL	1

TRAFFIC SIGNAL REMOVALS

SPV.0060.246	
REMOVING TRAFFIC SIGNALS (MLK & NORTH)	
LOCATION	EACH
MLK AT NORTH	1
TOTAL	1

TRAFFIC SIGNALS MOUNTING

SPV.0060.258	
TRAFFIC SIGNAL MOUNTING HARDWARE BLACK (LOCATION) MLK & NORTH	
LOCATION	EACH
MLK AT NORTH	1
TOTAL	1

TRAFFIC SIGNALS DETECTION SYSTEM

SPV.0060.224	
VEHICULAR VIDEO DETECTION SYSTEM	
LOCATION	EACH
1 CAMERA	1
TOTAL	1

TRAFFIC SIGNALS CABLE & WIRE

655.0515	
ELECTRICAL WIRE TRAFFIC SIGNALS	
LOCATION	TO LOCATION
CB1	TO SBF
SBF	TO SBF
SBG	TO SBF
SBH	TO SBI
SBI	TO SBJ
SBJ	TO SBA
SBA	TO SBB
SBB	TO SBC
SBC	TO SBD
SBD	TO SBE
SBE	TO CB1
TOTAL	

* ADDITIONAL QUANTITIES LISTED ELSEWHERE

TRAFFIC SIGNALS CABINET EQUIPMENT

SPV.0060.205		SPV.0060.212		SPV.0060.213		SPV.0060.221		SPV.0060.269	
ATC		FIBER OPTIC PATCH PANEL		ETHERNET SWITCH		EVP PHASE SELECTOR		VOICE INSTRUCTION	
CONTROLLER AND CABINET INSTALLED		EACH		EACH		EACH		EACH	
SIGNAL BASE	LOCATION	13+62', 61' R	1	1	1	1	1	1	1
NUMBER	LOCATION	13+62', 61' R	1	1	1	1	1	1	1
CB1	TOTAL	13+62', 61' R	1	1	1	1	1	1	1

TRAFFIC SIGNALS PULL BOXES

SPV.0060.303	
PULL BOXES 17-INCH X 30-INCH X 24-INCH	
PULL BOX	LOCATION
NUMBER	EACH
PB1	13+61.5', 46.5' R
PB2	13+47', 29' R
PB3	13+47', 33' L
PB4	13+65.5', 48.5' L
PB5	14+35', 49' L
PB6	14+50', 37' L
PB7	14+50', 30' R
PB8	14+34', 45' R
TOTAL	8

Addendum No. 01
ID 2568-00-72
Revised Sheet 77
October 1, 2026

PROJECT NO: 2568-00-72

HWY: N. DR MLK JR DR

COUNTY: MILWAUKEE

MISCELLANEOUS QUANTITIES

SHEET: 77

E

FILE NAME:

PLOT DATE:

PLOT BY:

PLOT NAME:

PLOT SCALE: 1:1

ALL ITEMS IN THIS SHEET ARE CATEGORY 0010

TRAFFIC SIGNALS QUANTITIES - N MLK JR DR & W NORTH AVE

TRAFFIC SIGNAL CONCRETE BASES

SIGNAL BASE NUMBER	LOCATION	654.0101		654.0120		SPV.0060.201	
		CONCRETE BASES TYPE 1	EACH	CONCRETE BASES TYPE 10-SPECIAL	EACH	INSTALL CITY PRECAST CONTROLLER BASE	EACH
CB1	13+62', 61' R	-	-	-	-	1	-
SBF	13+66', 49.5' R	-	-	1	-	-	-
SBG	13+61', 40' R	1	-	-	-	-	-
SBI	13+52', 33.5' L	-	-	1	-	-	-
SBA	14+33', 53.5' L	-	-	1	-	-	-
SBB	14+20.5', 45.5' L	1	-	-	-	-	-
SBD	14+28.5', 32' R	-	-	1	-	-	-
TOTAL		2	4	4	1		

TRAFFIC SIGNAL POLES

SIGNAL BASE NUMBER	SPV.0060.250		SPV.0060.251		SPV.0060.252		SPV.0060.253		SPV.0060.218		SPV.0060.223		SPV.0060.268	
	PEDESTAL BASES BLACK	EACH	POLES TYPE 10-SPECIAL BLACK	EACH	TRAFFIC SIGNAL STANDARDS ALUMINUM 3.5-FT BLACK	EACH	MONOTUBE ARMS 35-FT-SPECIAL BLACK	EACH	EVP 1 DIRECTION DETECTOR	EACH	EVP CONFIRMATION LIGHT	EACH	VOICE INSTRUCTION AUDIBLE PUSH BUTTON	
SBF	-	1	-	1	-	1	-	1	-	1	-	1	-	
SBG	1	-	1	-	1	-	1	-	-	-	-	-	1	
SBH	-	-	-	-	-	-	-	-	-	-	-	-	1	
SBI	-	1	-	1	-	1	-	1	1	1	1	1	1	
SBJ	-	-	-	-	-	-	-	-	-	-	-	-	1	
SBA	-	1	-	1	-	1	-	1	1	1	1	1	-	
SBB	1	-	1	-	1	-	1	-	-	-	-	-	1	
SBC	-	-	-	-	-	-	-	-	-	-	-	-	1	
SBD	-	1	-	1	-	1	-	1	1	1	1	1	1	
SBE	-	-	-	-	-	-	-	-	-	-	-	-	1	
TOTAL	2	4	4	2	4	4	4	4	4	4	4	4	8	

* ADDITIONAL QUANTITIES LISTED ELSEWHERE

TRAFFIC SIGNAL EAGES

SIGNAL HEAD NUMBER	SIGNAL BASE NUMBER	SPV.0060.254	EACH	TRAFFIC SIGNAL FACE 3S 12-INCH BLACK	EACH	TRAFFIC SIGNAL FACE 4S 12-INCH BLACK	EACH	TRAFFIC SIGNAL FACE 12-INCH BLACK	EACH	SPV.0060.255	EACH	PEDESTRIAN FACE	EACH	SPV.0060.256	EACH	PEDESTRIAN COUNTDOWN SIGNAL FACE 12-INCH BLACK	EACH	SPV.0060.257	EACH
1	SBE	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2	SBA	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3	SBA	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4	SBJ	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5	SBA	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
6	SBJ	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
7	SBF	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
8	SBF	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
9	SBE	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
10	SBF	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
11	SBH	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
12	SBD	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
13	SBD	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
14	SBC	-	-	-	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-
15	SBD	-	-	-	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-
16	SBC	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
17	SBI	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
18	SBI	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
19	SBH	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
20	SBI	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
21	SBI	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
22	SBC	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
23	SBA	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
24	SBE	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
25	SBD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
26	SBH	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
27	SBF	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
28	SBJ	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
TOTAL		18	2	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8

Addendum No. 01
ID 2568-00-72
Revised Sheet 78
October 1, 2026



Proposal Schedule of Items

Page 1 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0100 Removing Concrete Pavement	2,334.000 SY	_____.	_____.
0004	204.0155 Removing Concrete Sidewalk	1,193.000 SY	_____.	_____.
0006	204.0195 Removing Concrete Bases	22.000 EACH	_____.	_____.
0008	204.0215 Removing Catch Basins	1.000 EACH	_____.	_____.
0010	204.0245 Removing Storm Sewer (size) 01. 8-Inch	23.000 LF	_____.	_____.
0012	204.0250 Abandoning Manholes	1.000 EACH	_____.	_____.
0014	204.0255 Abandoning Catch Basins	7.000 EACH	_____.	_____.
0016	204.0291.S Abandoning Sewer	7.000 CY	_____.	_____.
0018	204.9060.S Removing (item description) 01. Poles	36.000 EACH	_____.	_____.
0020	204.9090.S Removing (item description) 01. Aerial Cable	3,900.000 LF	_____.	_____.
0022	205.0100 Excavation Common	640.000 CY	_____.	_____.
0024	205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	479.500 TON	_____.	_____.
0026	213.0100 Finishing Roadway (project) 01. 2568-00-71	1.000 EACH	_____.	_____.
0028	213.0100 Finishing Roadway (project) 02. 2568-00-72	1.000 EACH	_____.	_____.
0030	305.0110 Base Aggregate Dense 3/4-Inch	369.000 TON	_____.	_____.



Proposal Schedule of Items

Page 2 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	305.0120 Base Aggregate Dense 1 1/4-Inch	1,237.000 TON	_____.	_____.
0034	320.0145 Concrete Base 8-Inch	1,396.000 SY	_____.	_____.
0036	415.0080 Concrete Pavement 8-Inch	138.000 SY	_____.	_____.
0038	415.0110 Concrete Pavement 11-Inch	319.000 SY	_____.	_____.
0040	416.0610 Drilled Tie Bars	1,015.000 EACH	_____.	_____.
0042	416.0620 Drilled Dowel Bars	319.000 EACH	_____.	_____.
0044	455.0605 Tack Coat	99.000 GAL	_____.	_____.
0046	465.0105 Asphaltic Surface	310.000 TON	_____.	_____.
0048	601.0319 Concrete Curb & Gutter 19-Inch	983.000 LF	_____.	_____.
0050	601.0331 Concrete Curb & Gutter 31-Inch	35.000 LF	_____.	_____.
0052	601.0600 Concrete Curb Pedestrian	6.000 LF	_____.	_____.
0054	602.0410 Concrete Sidewalk 5-Inch	13,380.000 SF	_____.	_____.
0056	602.0515 Curb Ramp Detectable Warning Field Natural Patina	372.000 SF	_____.	_____.
0058	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	217.000 LF	_____.	_____.
0060	619.1000 Mobilization	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 3 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0062	624.0100 Water	25.000 MGAL	_____.	_____.
0064	625.0100 Topsoil	110.000 SY	_____.	_____.
0066	628.1905 Mobilizations Erosion Control	4.000 EACH	_____.	_____.
0068	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH	_____.	_____.
0070	628.7015 Inlet Protection Type C	8.000 EACH	_____.	_____.
0072	628.7020 Inlet Protection Type D	25.000 EACH	_____.	_____.
0074	631.0300 Sod Water	2.600 MGAL	_____.	_____.
0076	631.1000 Sod Lawn	110.000 SY	_____.	_____.
0078	637.2210 Signs Type II Reflective H	19.000 SF	_____.	_____.
0080	637.2220 Signs Type II Reflective SH	193.200 SF	_____.	_____.
0082	638.2102 Moving Signs Type II	13.000 EACH	_____.	_____.
0084	638.2602 Removing Signs Type II	25.000 EACH	_____.	_____.
0086	638.3000 Removing Small Sign Supports	1.000 EACH	_____.	_____.
0088	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0090	643.0300 Traffic Control Drums	9,640.000 DAY	_____.	_____.
0092	643.0420 Traffic Control Barricades Type III	2,688.000 DAY	_____.	_____.



Proposal Schedule of Items

Page 4 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0094	643.0705 Traffic Control Warning Lights Type A	5,366.000 DAY	_____.	_____.
0096	643.0900 Traffic Control Signs	7,040.000 DAY	_____.	_____.
0098	643.1050 Traffic Control Signs PCMS	120.000 DAY	_____.	_____.
0100	643.3150 Temporary Marking Line Removable Tape 4-Inch	4,470.000 LF	_____.	_____.
0102	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0104	644.1900.S Temporary Audible Message Devices	2,800.000 DAY	_____.	_____.
0106	646.1020 Marking Line Epoxy 4-Inch	2,960.000 LF	_____.	_____.
0108	646.2020 Marking Line Epoxy 6-Inch	1,690.000 LF	_____.	_____.
0110	646.3020 Marking Line Epoxy 8-Inch	915.000 LF	_____.	_____.
0112	646.5020 Marking Arrow Epoxy	30.000 EACH	_____.	_____.
0114	646.5220 Marking Symbol Epoxy	12.000 EACH	_____.	_____.
0116	646.9000 Marking Removal Line 4-Inch	3,080.000 LF	_____.	_____.
0118	646.9002 Marking Removal Line 6-Inch	2,630.000 LF	_____.	_____.
0120	646.9100 Marking Removal Line 8-Inch	960.000 LF	_____.	_____.
0122	646.9200 Marking Removal Line Wide	420.000 LF	_____.	_____.
0124	646.9300 Marking Removal Special Marking	41.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 5 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0126	650.4000 Construction Staking Storm Sewer	10.000 EACH	_____.	_____.
0128	650.5500 Construction Staking Curb Gutter and Curb & Gutter	1,378.000 LF	_____.	_____.
0130	650.8501 Construction Staking Electrical Installations (project) 01. 2568-00-71	1.000 EACH	_____.	_____.
0132	650.8501 Construction Staking Electrical Installations (project) 02. 2568-00-72	1.000 EACH	_____.	_____.
0134	650.9000 Construction Staking Curb Ramps	32.000 EACH	_____.	_____.
0136	650.9500 Construction Staking Sidewalk (project) 01. 2568-00-71	1.000 EACH	_____.	_____.
0138	650.9500 Construction Staking Sidewalk (project) 02. 2568-00-72	1.000 EACH	_____.	_____.
0140	650.9911 Construction Staking Supplemental Control (project) 01. 2568-00-71	1.000 EACH	_____.	_____.
0142	650.9911 Construction Staking Supplemental Control (project) 02. 2568-00-72	1.000 EACH	_____.	_____.
0144	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	75.000 LF	_____.	_____.
0146	652.0230 Conduit Rigid Nonmetallic Schedule 40 2 1/2-Inch	150.000 LF	_____.	_____.
0148	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	1,980.000 LF	_____.	_____.
0150	652.0615 Conduit Special 3-Inch	1,880.000 LF	_____.	_____.



Proposal Schedule of Items

Page 6 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0152	653.0905 Removing Pull Boxes	16.000 EACH	_____.	_____.
0154	654.0101 Concrete Bases Type 1	11.000 EACH	_____.	_____.
0156	654.0110 Concrete Bases Type 10	2.000 EACH	_____.	_____.
0158	654.0120 Concrete Bases Type 10-Special	10.000 EACH	_____.	_____.
0160	655.0230 Cable Traffic Signal 5-14 AWG	2,470.000 LF	_____.	_____.
0162	655.0240 Cable Traffic Signal 7-14 AWG	615.000 LF	_____.	_____.
0164	655.0270 Cable Traffic Signal 15-14 AWG	2,555.000 LF	_____.	_____.
0166	655.0280 Cable Traffic Signal 19-14 AWG	1,105.000 LF	_____.	_____.
0168	655.0305 Cable Type UF 2-12 AWG Grounded	4,265.000 LF	_____.	_____.
0170	655.0320 Cable Type UF 2-10 AWG Grounded	1,150.000 LF	_____.	_____.
0172	655.0515 Electrical Wire Traffic Signals 10 AWG	2,040.000 LF	_____.	_____.
0174	655.0900 Traffic Signal EVP Detector Cable	1,865.000 LF	_____.	_____.
0176	657.0100 Pedestal Bases	9.000 EACH	_____.	_____.
0178	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	7.000 EACH	_____.	_____.
0180	657.0350 Poles Type 10	2.000 EACH	_____.	_____.
0182	657.0352 Poles Type 10-Special	6.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 7 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0184	657.0405 Traffic Signal Standards Aluminum 3.5-FT	5.000 EACH	_____.	_____.
0186	657.0420 Traffic Signal Standards Aluminum 13-FT	4.000 EACH	_____.	_____.
0188	657.0525 Monotube Arms 25-FT	2.000 EACH	_____.	_____.
0190	657.0536 Monotube Arms 35-FT-Special	6.000 EACH	_____.	_____.
0192	658.0173 Traffic Signal Face 3S 12-Inch	48.000 EACH	_____.	_____.
0196	658.0412 Pedestrian Signal Face 12-Inch	24.000 EACH	_____.	_____.
0198	658.5070 Signal Mounting Hardware (location) 01. MLK & Wright	1.000 EACH	_____.	_____.
0200	658.5070 Signal Mounting Hardware (location) 02. MLK & Clarke	1.000 EACH	_____.	_____.
0202	658.5070 Signal Mounting Hardware (location) 03. MLK & Center	1.000 EACH	_____.	_____.
0206	659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor	110.000 EACH	_____.	_____.
0208	661.0201 Temporary Traffic Signals for Intersections (location) 01. MLK & Wright	1.000 EACH	_____.	_____.
0210	661.0201 Temporary Traffic Signals for Intersections (location) 02. MLK & Clarke	1.000 EACH	_____.	_____.
0212	661.0201 Temporary Traffic Signals for Intersections (location) 03. MLK & Center	1.000 EACH	_____.	_____.
0214	661.0201 Temporary Traffic Signals for Intersections (location) 04. MLK & North	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 8 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0216	690.0150 Sawing Asphalt	102.000 LF	_____.	_____.
0218	690.0250 Sawing Concrete	2,347.000 LF	_____.	_____.
0220	715.0720 Incentive Compressive Strength Concrete Pavement	1,000.000 DOL	1.00000	1,000.00
0222	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,400.000 HRS	5.00000	7,000.00
0224	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	3,600.000 HRS	5.00000	18,000.00
0226	SPV.0060 Special 001. Utility Line Opening	15.000 EACH	_____.	_____.
0228	SPV.0060 Special 002. Adjusting Water Valve Boxes	40.000 EACH	_____.	_____.
0230	SPV.0060 Special 102. Inlet Covers Type MS 57	11.000 EACH	_____.	_____.
0232	SPV.0060 Special 103. Manhole Covers Type MS 58-A	6.000 EACH	_____.	_____.
0234	SPV.0060 Special 110. Catch Basin Type 44A	10.000 EACH	_____.	_____.
0236	SPV.0060 Special 201. Install City Precast Controller Base	4.000 EACH	_____.	_____.
0238	SPV.0060 Special 205. ATC Controller and Cabinet Installed	4.000 EACH	_____.	_____.
0240	SPV.0060 Special 212. Fiber Optic Patch Panel	4.000 EACH	_____.	_____.
0242	SPV.0060 Special 213. Ethernet Switch	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 9 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0244	SPV.0060 Special 215. Electrical Service Pedestal	2.000 EACH	_____.	_____.
0246	SPV.0060 Special 218. EVP 1 Direction Detector	12.000 EACH	_____.	_____.
0248	SPV.0060 Special 221. EVP Phase Selector Card 4 Channel	4.000 EACH	_____.	_____.
0250	SPV.0060 Special 223. EVP Confirmation Light	12.000 EACH	_____.	_____.
0252	SPV.0060 Special 224. Vehicular Video Detection System 1-Camera	1.000 EACH	_____.	_____.
0254	SPV.0060 Special 228. Electrical Riser	12.000 EACH	_____.	_____.
0256	SPV.0060 Special 243. Removing Traffic Signals (MLK & Wright)	1.000 EACH	_____.	_____.
0258	SPV.0060 Special 244. Removing Traffic Signals (MLK & Clarke)	1.000 EACH	_____.	_____.
0260	SPV.0060 Special 245. Removing Traffic Signals (MLK & Center)	1.000 EACH	_____.	_____.
0262	SPV.0060 Special 246. Removing Traffic Signals (MLK & North)	1.000 EACH	_____.	_____.
0264	SPV.0060 Special 267. Pedestrian Countdown Signal Face 12-Inch	24.000 EACH	_____.	_____.
0266	SPV.0060 Special 268. Voice Instruction Audible Push Button	32.000 EACH	_____.	_____.
0268	SPV.0060 Special 269. Voice Instruction Audible Control Unit	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 10 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0270	SPV.0060 Special 280. Round Aluminum Sign Post System in Soft Surface 7-FT	1.000 EACH	_____.	_____.
0272	SPV.0060 Special 284. Round Aluminum Sign Post System in Concrete Surface 7-FT	13.000 EACH	_____.	_____.
0274	SPV.0060 Special 285. Round Aluminum Sign Post System in Concrete Surface 10-FT	1.000 EACH	_____.	_____.
0276	SPV.0060 Special 288. Sign Mounting Hardware on Existing Pole	8.000 EACH	_____.	_____.
0278	SPV.0060 Special 290. Street Name Sign Mounting Hardware on Existing Pole	4.000 EACH	_____.	_____.
0280	SPV.0060 Special 291. Street Name Sign Mounting Hardware on Mast Arm	12.000 EACH	_____.	_____.
0282	SPV.0060 Special 292. Sign Mounting Hardware on Round Aluminum Sign Post	15.000 EACH	_____.	_____.
0284	SPV.0060 Special 302. Pull Boxes 13-Inch x 24-Inch x 24-Inch	36.000 EACH	_____.	_____.
0286	SPV.0060 Special 303. Pull Boxes 17-Inch x 30-Inch x 24-Inch	32.000 EACH	_____.	_____.
0288	SPV.0060 Special 320. Poles Type 25-AL-BD Aluminum	4.000 EACH	_____.	_____.
0290	SPV.0060 Special 321. Poles Type 25-AL-BD Black	1.000 EACH	_____.	_____.
0292	SPV.0060 Special 322. Poles Type 30-AL-BD Aluminum	3.000 EACH	_____.	_____.
0294	SPV.0060 Special 323. Poles Type 30-AL-BD Black	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 11 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0296	SPV.0060 Special 324. Poles Wood 40-FT	20.000 EACH	_____.	_____.
0298	SPV.0060 Special 334. Inline 5A Fast Acting Fuse with Holder	60.000 EACH	_____.	_____.
0300	SPV.0060 Special 339. Primary or Secondary Riser	13.000 EACH	_____.	_____.
0302	SPV.0060 Special 342. Submersible Multitap 3-Port Pre-Insulated Connector	187.000 EACH	_____.	_____.
0304	SPV.0060 Special 343. Submersible Multitap 4-Port Pre-Insulated Connector	55.000 EACH	_____.	_____.
0306	SPV.0060 Special 345. Luminaire Arms Single Member 6-FT	7.000 EACH	_____.	_____.
0308	SPV.0060 Special 346. Luminaire Arms Single Member 6-FT WP Mount	27.000 EACH	_____.	_____.
0310	SPV.0060 Special 353. Equipment Grounding Electrode	46.000 EACH	_____.	_____.
0312	SPV.0060 Special 355. Install A21-A26 City Furnished Mounting Clamp Single Bracket	3.000 EACH	_____.	_____.
0314	SPV.0060 Special 357. Install A31 City Furnished Mounting Clamp Single Bracket	9.000 EACH	_____.	_____.
0316	SPV.0060 Special 376. Luminaire Utility 3LED2	28.000 EACH	_____.	_____.
0318	SPV.0060 Special 390. Milwaukee Light Base Type 1	5.000 EACH	_____.	_____.
0320	SPV.0060 Special 399. Transformer Bases Breakaway 11 1/2-Inch Bolt Circle Black	5.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 12 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0322	SPV.0060 Special 425. Installing Conduit into Existing Manhole	2.000 EACH	_____.	_____.
0324	SPV.0060 Special 430. Adjusting CUC Manhole Cover Using EPP System	6.000 EACH	_____.	_____.
0326	SPV.0060 Special 801. Poles Type H17	9.000 EACH	_____.	_____.
0328	SPV.0060 Special 804. Poles Type 15-OCT	5.000 EACH	_____.	_____.
0330	SPV.0060 Special 818. Poles Type A26-BD	2.000 EACH	_____.	_____.
0332	SPV.0060 Special 819. Poles Type A31-BD	9.000 EACH	_____.	_____.
0334	SPV.0060 Special 820. Concrete Base Type 5 Modified	12.000 EACH	_____.	_____.
0336	SPV.0060 Special 821. Concrete Base Type 2 Modified	14.000 EACH	_____.	_____.
0338	SPV.0060 Special 865. Luminaire Historic Milwaukee Harp LED 1	14.000 EACH	_____.	_____.
0340	SPV.0060 Special 867. Luminaire Historic Milwaukee Lantern LED 3	28.000 EACH	_____.	_____.
0342	SPV.0090 Special 010. Concrete Curb & Gutter Integral 19-Inch	279.000 LF	_____.	_____.
0344	SPV.0090 Special 240. Electrical Cable 3#4/1#8 XLP	135.000 LF	_____.	_____.
0346	SPV.0090 Special 302. Electrical Cable Type 3#6 AL	1,250.000 LF	_____.	_____.



Proposal Schedule of Items

Page 13 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0348	SPV.0090 Special 304. Electrical Cable Type 2#2/1#4 AL	575.000 LF	_____.	_____.
0350	SPV.0090 Special 319. Liquidtight Flexible Nonmetallic Conduit 1 1/2-Inch	700.000 LF	_____.	_____.
0352	SPV.0090 Special 322. Electrical Cable Type 4#6/1#8 XLP	1,900.000 LF	_____.	_____.
0354	SPV.0090 Special 324. Electrical Cable Type 4#2/1#8 XLP	1,950.000 LF	_____.	_____.
0356	SPV.0090 Special 325. Conduit 3-Inch HDPE Schedule 40	3,600.000 LF	_____.	_____.
0358	SPV.0090 Special 401. 1-Duct Conduit, Cement Encased, 4-Inch Rigid Nonmetallic Conduit DB-60	83.000 LF	_____.	_____.
0360	SPV.0090 Special 705. Marking Crosswalk Epoxy Block Style 12-Inch	1,700.000 LF	_____.	_____.
0362	SPV.0090 Special 706. Marking Stop Line Epoxy 24-Inch	435.000 LF	_____.	_____.
0364	SPV.0060 Special 250. Pedestal Bases Black	2.000 EACH	_____.	_____.
0366	SPV.0060 Special 251. Poles Type 10-Special Black	4.000 EACH	_____.	_____.
0368	SPV.0060 Special 252. Traffic Signal Standards Aluminum 3.5-FT Black	2.000 EACH	_____.	_____.
0370	SPV.0060 Special 253. Monotube Arms 35-FT- Special Black	4.000 EACH	_____.	_____.
0372	SPV.0060 Special 254. Traffic Signal Face 3S 12- Inch Black	18.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 14 of 14

Proposal ID: 20261013007 Project(s): 2568-00-71, 2568-00-72

Federal ID(s): WISC 2027006, WISC 2027005

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0374	SPV.0060 Special 255. Traffic Signal Face 4S 12-Inch Black	2.000 EACH	_____.	_____.
0376	SPV.0060 Special 256. Pedestrian Signal Face 12-Inch Black	8.000 EACH	_____.	_____.
0378	SPV.0060 Special 257. Pedestrian Countdown Signal Face 12-Inch Black	8.000 EACH	_____.	_____.
0380	SPV.0060 Special 258. Traffic Signal Mounting Hardware Black (Location) MLK & North	1.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.