



Wisconsin Department of Transportation

September 23, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #22: 1020-05-63, WISC 2027009
Menomonie – Eau Claire
Wilson Creek to Red Cedar River
IH 094
Dunn County

1021-01-78
Baldwin - Menomonie
East Br Wilson Cr Bridge B-17-0051
IH 094
Dunn County

Letting of October 13, 2026

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
7	Utilities.

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
2	General Notes (add utility contact information for Level 3.)
182	Plan Sheet (revise utility crossing ownership and label.)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01
1020-05-63 & 1021-01-78
September 23, 2026

Special Provisions

7. Utilities.

Replace entire article language with the following:

This contract comes under the provision of Administrative Rule Trans 220.

The utility work plan includes additional detailed information regarding the location of known discontinued, relocated, or removed utility facilities. These can be requested from the department during the bid preparation process, or from the project engineer after the contract has been awarded and executed.

Some of the utility work described below is dependent on prior work being performed by the contractor at a specific site. In such situations, provide the engineer and the affected utility a good faith notice of when the utility is to start work at the site. Provide this notice 14 to 16 calendar days in advance of when the prior work will be completed and the site will be available to the utility. Follow-up with a confirmation notice to the engineer and the utility not less than 3 working days before the site will be ready for the utility to begin its work.

stp-107-065 (20240703)

Any utility facility locations (stations, offsets, elevations, depths) listed in this article are approximate.

ID 1020-05-63

City of Menomonie (Water)

The city will remove the existing water main that hangs from the underside of the Wilson Street Bridge (B-17-40) in its entirety. Insulation and wrap attached to water main will be removed with the water main. Hangars connecting the water main to the bridge will be torched and/or ground off as close as possible to bottom side of the bridge deck. Water main will be cut and capped where it enters the embankment at the north and south abutments. The city plans to begin removals in January 2027 and complete the work prior to construction.

Level 3 Communications LLC (Communication Line)

Level 3 COMM LLC has an underground fiber optic facility that crosses IH 94 at Station 153+75 WB. The fiber optic cables connect to a hand hole located in the ditch backslope near Station 153+75 WB, 75' LT. The hand hole will remain in service and must be worked around during ditch cleaning operations.

Xcel Energy (Gas/Petroleum)

Xcel Energy has an 8-Inch steel high pressure gas main that crosses IH 94 at Station 88+00EB.

Schedule Xcel Energy watchdog to observe guardrail and excavation work near the gas main. Provide notice to Xcel Energy Senior Operations Coordinator Reed Olson at (507) 457-1239.

The following utility owners have facilities within the project area; however, no conflicts are anticipated:

ID 1020-05-63

24-7 Telcom (Communication Line)

AT&T Legacy (Communication Line)

AT&T Wisconsin (Communication Line)

Centurylink (Communication Line)

City of Menomonie (Sanitary Sewer)
Xcel Energy (Electricity)
Xcel Energy (Electricity Transmission)
ID 1020-01-78
AT&T Legacy (Communication Line)
Centurylink (Communication Line)

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 2, 182.

END OF ADDENDUM

24-7 TELECOM
COMMUNICATION LINE
BRADLEY SCHMIDTKNECHT
PO BOX 247
DOWNSVILLE, WI 54735
PHONE: (715) 231-0504 (OFFICE)
PHONE: (715) 306-1914 (CELL)
EMAIL: BRADS@WWT.COOP

AT&T LEGACY
COMMUNICATION LINE
KENNETH NINE
110 N. MAIN ST.
CLIVER, IN 46511
PHONE: (574) 842-8830 (OFFICE)
PHONE: (574) 904-6336 (CELL)
EMAIL: KNINE@MCEANC.COM

AT&T WISCONSIN
COMMUNICATION LINE
RICK PODOLAK
304 S DEWEY ST - 4TH FLOOR
EAU CLAIRE, WI 54701
PHONE: (715) 410-0656
EMAIL: RP4514@ATT.COM

UTILITIES CONTACTS

CITY OF MENOMONIE
SANITARY SEWER
DAVID SCHOFIELD
800 WILSON AVE
MENOMONIE, WI 54751-2734
PHONE: (715) 232-2221, EXT 1020
EMAIL: DSCHOFIELD@MENOMONIE.WI.GOV

LEVEL 3
COMMUNICATION LINE
RYAN HEIKILA
715 2ND ST N
MINNEAPOLIS, MN 55401
PHONE: (612) 741-2782
EMAIL: RYAN.HEIKILA@UMEN.COM

XCEL ENERGY
ELECTRICITY / TRANSMISSION
RILEY MOLDENHAUER
1414 W HAMILTON AVENUE, P.O. BOX 8
EAU CLAIRE, WI 54702-0008
PHONE: (715) 559-0164
EMAIL: RILEY.J.MOLDENHAUER@XCELENERGY.COM
CC: DAWN.SCHULTZ@XCELENERGY.COM

CITY OF MENOMONIE
WATER
DAVID SCHOFIELD
800 WILSON AVE
MENOMONIE, WI 54751-2734
PHONE: (715) 232-2221 EXT 1020
EMAIL: DSCHOFIELD@MENOMONIE.WI.GOV

XCEL ENERGY
GAS / PETROLEUM
JOHN KELSER
1414 W HAMILTON AVE, P.O. BOX 8
EAU CLAIRE, WI 54702
PHONE: (715) 737-6020
EMAIL: JOHN.KELSER@XCELENERGY.COM
CC: DAWN.SCHULTZ@XCELENERGY.COM

XCEL ENERGY
ELECTRICITY
JOHN KELSER
1414 W HAMILTON AVE, P.O. BOX 8
EAU CLAIRE, WI 54702
PHONE: (715) 737-6020
EMAIL: JOHN.KELSER@XCELENERGY.COM
CC: DAWN.SCHULTZ@XCELENERGY.COM

RUNOFF COEFFICIENT TABLE

	HYDROLOGIC SOIL GROUP			
	A	B	C	D
LAND USE:	SLOPE RANGE (PERCENT)	SLOPE RANGE (PERCENT)	SLOPE RANGE (PERCENT)	SLOPE RANGE (PERCENT)
	0-2 2-6	0-2 2-6	0-2 2-6	0-2 2-6
ROW CROPS:	.08 .22	.16 .30	.12 .38	.06 .34
	.22 .30	.38 .44	.24 .37	.19 .50
MEDIAN STRIPTURF:	.19 .24	.20 .26	.23 .30	.20 .27
	.20 .26	.22 .28	.23 .30	.20 .32
SIDE SLOPEURF:	.25 .32	.27 .34	.30 .36	.27 .38
	.32 .38	.34 .40	.36 .42	.38 .44
PAVEMENT:				
ASPHALT:		.70 - .95		
CONCRETE:		.80 - .95		
BRICK:		.70 - .80		
DRIVES, WALKS:		.75 - .85		
ROOFS:		.75 - .95		
GRAVEL ROADS, SHOULDER:		.40 - .60		

TOTAL PROJECT AREA = 53.767 ACRES
TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 3.146 ACRES

WISCONSIN DNR LIAISON

LEAH NICOL
WEST CENTRAL REGION
1300 WEST CLAREMONT AVENUE
EAU CLAIRE, WI 54701
PHONE: (715) 836-2055
EMAIL: LEAH.NICOL@WISCONSIN.GOV

DESIGN PROJECT MANAGER

ADAM HETRICK, P.E.
718 W CLAREMONT AVE.
EAU CLAIRE, WI 54701
PHONE: (715) 836-2055
EMAIL: ADAM.HETRICK@DOT.WI.GOV

DESIGN CONTACT

TAMAY TUCKER, P.E.
CBSSQUAREDINC.COM
2500 E ENTERPRISE AVE, SUITE A
APPLETON, WI 54913
PHONE: (262) 613-8999
EMAIL: TUCKER@CBSSQUAREDINC.COM

GENERAL NOTES

THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

CONTRACTOR WILL BE RESPONSIBLE FOR RESHAPING AND SEEDING ANY PREVIOUSLY GRASSED AREAS WHICH ARE DISTURBED BY OPERATIONS, OUTSIDE OF THE NORMAL CONSTRUCTION LIMITS.

HMA PAVEMENT WEIGHT CALCULATIONS ARE BASED ON 112 LBS/SY/IN.

RIGHT OF WAY INFORMATION SHOWN ON THE PLANS IS APPROXIMATE

RADIUS DIMENSIONS FOR THE CURB AND GUTTER ARE TO THE FLANGE LINE UNLESS OTHERWISE NOTED.

CURVE DATA IS BASED ON THE RADIUS DEFINITION.

PAVEMENT REMOVAL WILL BE TO THE NEAREST JOINT OR A SAWED EDGE WILL BE REQUIRED AS DIRECTED BY THE ENGINEER.

PIPE AND INLET ELEVATIONS AS SHOWN ON THE PLANS MAY BE ADJUSTED BY THE ENGINEER TO FIT EXISTING FIELD CONDITIONS

CURB AND GUTTER PLAN GRADES ARE AT THE FLANGE LINE UNLESS OTHERWISE NOTED.

THE PROPOSED SHOULDER WIDTH SHOWN IN THE TYPICAL SECTIONS ARE MINIMUM WIDTH. PERPETUATE EXISTING SHOULDER THAT ARE WIDER THAN WHAT IS SHOWN IN THE TYPICAL SECTIONS.

THE CONTRACTOR'S PAVING OPERATION SHALL BE CONSISTENT WITH THE TYPICAL SECTIONS AND CONSTRUCTED TO PREVENT LONGITUDINAL JOINTS FROM BEING LOCATED WITHIN A DRIVING, TURNING, PASSING, OR PARKING LANE.

CONTRACTOR SHALL MAINTAIN ACCESS TO ALL DRIVEWAYS AT ALL TIMES EXCEPT WHEN PAVING OR PIPE LAYING OPERATIONS REQUIRE THE DRIVEWAY TO BE CLOSED. ACCESS TO DRIVEWAYS SHALL BE RE-ESTABLISHED IMMEDIATELY AFTER OPERATIONS ARE COMPLETED. ACCESS SHALL BE PROVIDED DURING ALL NON-WORKING HOURS.

DO NOT DRIVE OR STORE EQUIPMENT, OR STORE CONSTRUCTION MATERIALS IN ENVIRONMENTALLY SENSITIVE AREAS, WETLANDS OR WATERWAYS.

ORDER OF SECTION 2 DETAIL SHEETS

GENERAL NOTES
PROJECT OVERVIEW
TYPICAL SECTIONS
CONSTRUCTION DETAILS
GUARDRAIL DETAILS
CURB RAMP DETAILS
FMS (BY WISDOT)
EROSION CONTROL
PIPE DETAILS
PERMANENT SIGNING
LIGHTING REMOVALS (BY KL ENGINEERING)
LIGHTING PLAN (BY KL ENGINEERING)
PAVEMENT MARKING
ADVANCED WARNING SIGNING
TRAFFIC CONTROL

Addendum No. 01
ID 1020-05-63/1021-01-78
Revised Sheet 2
September 23, 2026

DIGGERS HOTLINE
Dial 811 or (800)242-8511
www.DiggersHotline.com

Addendum No. 01
ID 1020-05-63
Revised Sheet 182
September 23, 2026



