



Wisconsin Department of Transportation

September 30, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #26: 1610-01-81
Medford - Prentice
CTH M E to STH 102
STH 13
Taylor County

Letting of October 13, 2026

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
643.3165	Temporary Marking Line Paint 6-Inch	LF	41,319	-18,357	22,962

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
21	Miscellaneous Quantities (Quantity table for Pavement Marking Items changed to show reduction in total quantities for Item 643.3165)

Schedule of Items

Attached, dated September 30, 2026, are the revised Schedule of Items Page 4.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 21.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

PAVEMENT MARKING ITEMS
643.3165

		646.2040		646.4040		646.6120	
		MARKING LINE		MARKING LINE		MARKING STOP LINE	
CATEGORY	STATION	TO	STATION	LOCATION	TEMPORARY MARKING LINE PAINT 6-INCH *		MARKING STOP LINE EPOXY 18-INCH
					6-INCH (YELLOW)	10-INCH (WHITE)	
0010	850+66	-	915+00	STH 13	4,826	5,022	12,577
0010	915+00	-	980+00	STH 13	4,875	3,766	12,899
0010	980+00	-	1044+00	STH 13	4,800	5,583	12,800
0010	1044+00	-	1105+00	STH 13	4,575	4,222	11,624
0010	1105+00	-	1155+00	STH 13	3,750	7,115	9,674
0010	20+00	-	21+81	STH 102	136	302	231
				NORTH ST		109	34
				SUBTOTAL	22,962	59,805	892
				TOTAL 0010			68

*APPLIED TO MILLED SURFACE AND LOWER LAYER OF HMA (CENTER SKIPS ONLY) AND
TO TOP SURFACE PRIOR TO INSTALLATION OF RUMBLE STRIPS (CENTER SKIPS ONLY).
**APPLIED TO TOP SURFACE AFTER INSTALLATION OF RUMBLE STRIPS.

Addendum No. 01
ID 1610-01-81
Revised Sheet 21
September 30, 2026

CONSTRUCTION STAKING ITEMS

		650.4500		650.5000		650.6000		650.8000		650.9911.01		650.9920	
		CONSTRUCTION STAKING		CONSTRUCTION STAKING		CONSTRUCTION STAKING		CONSTRUCTION STAKING		CONSTRUCTION STAKING		CONSTRUCTION STAKING	
CATEGORY	STATION	TO	STATION	LOCATION	SUBGRADE LF	BASE LF	PIPE CULVERTS EACH	RESURFACING REFERENCE LF	SUPPLEMENTAL CONTROL (01 1610-01-81) EACH	SLOPE STAKES LF			
0010	852+27	-	853+37	110	110	110				110			
0010	1030+46	-	1031+59	113	113					113			
0010	852+82.0						1						
0010	997+83.4						1						
0010	1031+02.5						1						
0010	1043+89.1						1						
0010	1096+43.2						1						
0010	850+66	-	1155+00					30,434	1				
0010	20+00	-	21+81					181					
TOTAL 0010					223	223	5	30,615	1			223	

PUBLIC LAND REFERENCE MONUMENT VERIFY AND RESET

CATEGORY	STATION	LOCATION	REMARKS
0010	955+92.91	18.09' RT	QTR CRNR - REBAR W ALUM CAP 12" BELOW GRADE
0010	1008+47.62	0.06' LT	QTR CRNR - PK NAIL
0010	1060+78.08	18.89' LT	QTR CRNR - COTTON GIN SPIKE
0010	1116+31.00	42.32' RT	QTR CRNR - 2.5" CONC FILLED IRON PIPE 7" BELOW GRADE
TOTAL 0010		4	

SAWING ASPHALT

CATEGORY	STATION	LOCATION	REMARKS
0010	852+82.0	60	PIPE REPLACEMENT
0010	1031+02.5	60	PIPE REPLACEMENT
TOTAL 0010		120	

DITCH CLEANING

CATEGORY	STATION	LOCATION	REMARKS
0010	21+01.1	50	SPV 0090.01
TOTAL 0010		50	

PROJECT NO: 1610-01-81

HWY: STH 13

COUNTY: TAYLOR

MISCELLANEOUS QUANTITIES

SHEET 21

E

FILE NAME: C:\USERS\BMMITTON\DRIVE - RISE\ENGINEERING\COMP\PROJECTS\1610-01-11_STH 13 TAYLOR CO\DESIGN\1610-01-11\11SHEETS\030201-MOLDWG LAYOUT NAME - 04
PLOT DATE: 9/29/2026 4:04 PM
PLOT BY: BRIAN SMITS
PLOT NAME: 1"=1'
WISDOT/CADDIS SHEET 12



Proposal Schedule of Items

Page 4 of 6

Proposal ID: 20261013026 Project(s): 1610-01-81

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0088	625.0500 Salvaged Topsoil	1,084.000 SY	_____.	_____.
0090	628.1504 Silt Fence	1,768.000 LF	_____.	_____.
0092	628.1520 Silt Fence Maintenance	3,536.000 LF	_____.	_____.
0094	628.1905 Mobilizations Erosion Control	4.000 EACH	_____.	_____.
0096	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____.	_____.
0098	628.2008 Erosion Mat Urban Class I Type B	1,389.000 SY	_____.	_____.
0100	628.7555 Culvert Pipe Checks	138.000 EACH	_____.	_____.
0102	629.0210 Fertilizer Type B	2.100 CWT	_____.	_____.
0104	630.0130 Seeding Mixture No. 30	89.000 LB	_____.	_____.
0106	630.0500 Seed Water	43.000 MGAL	_____.	_____.
0108	633.5200 Markers Culvert End	11.000 EACH	_____.	_____.
0110	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0112	643.0300 Traffic Control Drums	431.000 DAY	_____.	_____.
0114	643.0900 Traffic Control Signs	2,175.000 DAY	_____.	_____.
0116	643.3165 Temporary Marking Line Paint 6-Inch	22,962.000 LF	_____.	_____.
0118	643.5000 Traffic Control	1.000 EACH	_____.	_____.