

## Table of Contents

### PART 100 General Requirements and Covenants

<u>Section 101 General Information, Definitions, and Terms</u> .....	2
<u>Section 102 Bidding Requirements and Conditions</u> .....	10
Revise 102.6.2 to update process for DBE Commitment submittal.	
<u>Section 103 Contract Award and Execution</u> .....	15
<u>Section 104 Scope of Work</u> .....	17
<u>Section 105 Control of the Work</u> .....	28
<u>Section 106 Control of Materials</u> .....	34
<u>Section 107 Legal Relations and Responsibility to the Public</u> .....	40
<u>Section 108 Prosecution and Progress</u> .....	49
Add 108.9.4.1 for winter suspension for completion date contracts. This change was implemented via ASP-6 with the November 2023 letting.	
Revise 108.10.2.1(3) to remove former item 6 and renumber remaining item. This change was implemented via ASP-6 with the January 2024 letting.	
Revise 108.10.3 to remove text from 108.10.3(1) and 108.10.3(2) item 5 due to changes to Trans 220 of the Wisconsin Administrative Code. This change was implemented via ASP-6 with the January 2024 letting.	
<u>Section 109 Measurement and Payment</u> .....	62

### PART 200 Earthwork

<u>Section 201 Clearing and Grubbing</u> .....	72
<u>Section 202 Roadside Clearing</u> .....	75
<u>Section 203 Removing Old Culverts and Bridges</u> .....	76
<u>Section 204 Removing or Abandoning Miscellaneous Structures</u> .....	81
Revise 204.3.2.2(13) to clarify information regarding removing storm sewer. Add paragraph (14) for new bid item "Removing Cable Barrier".	
Revise 204.4(7) to add information relating to new bid item Removing Cable Barrier. Revise paragraph (19) to clarify information for Removing Storm Sewer bid item.	
Add bid item to 204.5 for removing cable barrier.	
<u>Section 205 Roadway and Drainage Excavation</u> .....	87
<u>Section 206 Excavation for Structures</u> .....	95
<u>Section 207 Embankment</u> .....	100
<u>Section 208 Borrow</u> .....	103
<u>Section 209 Granular Backfill</u> .....	106
<u>Section 210 Structure Backfill</u> .....	108
<u>Section 211 Preparing the Foundation</u> .....	110
<u>Section 213 Finishing Roadway</u> .....	113
<u>Section 214 Obliterating Old Road</u> .....	115

### PART 300 Bases, Subbases, and Subgrade Aggregates

<u>Section 301 Base, Subbase, and Subgrade Aggregate</u> .....	118
<u>Section 305 Dense-Graded Base</u> .....	123
<u>Section 310 Open-Graded Base</u> .....	126
Revise 310.2(2) reference to add material gradation requirements for coarse aggregate. This change was implemented via ASP-6 with the November 2023 letting.	
<u>Section 311 Breaker Run</u> .....	128
<u>Section 312 Select Crushed Material</u> .....	129
<u>Section 313 Pit Run</u> .....	130
<u>Section 315 Asphaltic Base</u> .....	131
<u>Section 320 Concrete Base</u> .....	132
<u>Section 325 Pulverized and Re-laid Pavement</u> .....	134
<u>Section 330 Milled and Re-laid Pavement</u> .....	135
<u>Section 335 Rubblized Pavement</u> .....	136
<u>Section 340 Cracked and Seated Pavement</u> .....	138

<u>Section 350 Subbase .....</u>	139
<u>Section 390 Base Patching .....</u>	141

Revise 309.3.4(1) to update link from 416.3.8 to 416.3.7. This change was implemented via ASP-6 with the November 2023 letting.

Revise 309.4 measurement information for base patching items. This change was implemented via ASP-6 with the November 2023 letting.

Revise 390.5 to retire "Base Patching" bid item by the SY. Add Bid item 390.0100 "Removing Pavement for Base Patching" by the CY. Retire "Base Patching Ashphalitic" bid item by SY. Add bid item 390.0305 for "Base Patching Concrete HES" by the CY. Retire bid item for "Base Patching Concrete SHES" by the SY and add bid item number 390.0405 "Base Patching Concrete SHES" by the CY. Update descriptions for base patching items. This change was implemented via ASP-6 with the November 2023 letting.

## PART 400 Pavements

<u>Section 405 Coloring and Stamping Concrete .....</u>	144
<u>Section 415 Concrete Pavement.....</u>	147
<u>Section 416 Concrete Pavement – Repair and Replacement.....</u>	159
<u>Section 420 Diamond Grinding .....</u>	163
<u>Section 450 General Requirements for Asphaltic Pavements .....</u>	165
<u>Section 455 Asphaltic Materials.....</u>	173
<u>Section 460 Hot Mix Asphalt Pavement .....</u>	177
Revise 460.2.8.2.1.3.1(4) test methods for asphalt content (AC) in percent. This change was implemented via ASP-6 with the November 2023 letting.	
Add test method information to 460.2.8.3.1.4(3) if using ignition oven to determine AC. This change was implemented via ASP-6 with the November 2023 letting.	
Add information to 460.3.3.2(1) and (3). Add reference to CMM, WTM, and WTP H-002. WTP H-002 contains the subplot layouts formerly in CMM 815. Definition of a lot is now defined here (460.3.3.2(3)) instead of CMM. This change was implemented via ASP-6 with the November 2023 letting.	
<u>Section 465 Asphaltic Surface .....</u>	191
<u>Section 475 Seal Coat.....</u>	193

## PART 500 Structures

<u>Section 501 Concrete.....</u>	196
<u>Section 502 Concrete Bridges .....</u>	214
Revise 502.2.7.3(2) to change information for expansion devices from polychloroprene to elastomeric strip seals.	
<u>Section 503 Prestressed Concrete Members.....</u>	235
Revise 503.2.2(5) reference for coarse aggregate material gradation. This change was implemented via ASP-6 with the November 2023 letting.	
<u>Section 504 Culverts, Retaining Walls, and Endwalls .....</u>	241
<u>Section 505 Steel Reinforcement.....</u>	243
<u>Section 506 Steel Bridges .....</u>	248
Revise 506.2.7 to update references to current edition of American Welding Society (AWS) D1.5 Bridge Code.	
Revise 506.3.3 language that is no longer required by ASTM A6.	
Revise 506.3.8 to require preheats from approved repair Welding Procedure Specification (WPS). Remove defect size limit. Engineer approval still required.	
Revise 506.3.12.3 connection information, update bolt tension information on Table 506-1 to match Research Council on Structural (RCSC) table, change Rotational Capacity Testing to manufacturer only, unless the fastener condition change prior to installation. Add time limit for pre-installation verification testing, require repeat RoCAP and PIV if fastener condition changes, and that engineer may require additional testing under certain conditions.	
Revise 506.3.12.3.2 to remove under-rotation tolerance per RCSC.	
Revise 506.3.19 to update reference information and remove sentence from 506.3.19.2(2).	
Revise 506.3.20 to update reference information.	
Revise 506.3.23 to reorganize information and add information that must be displayed on shipping container labels.	
<u>Section 507 Timber Structures .....</u>	267
<u>Section 509 Concrete Overlay and Structure Repair .....</u>	274
<u>Section 511 Temporary Shoring .....</u>	279
<u>Section 512 Steel Sheet Piling .....</u>	280

<u>Section 513 Railing</u>	282
<u>Section 514 Floor Drains, Deck Drains, and Downspouts</u>	285
<u>Section 515 Steel Grid Floors</u>	287
<u>Section 516 Waterproofing</u>	288
<u>Section 517 Paint and Painting</u>	290
<u>Section 519 Brick Masonry and Concrete Brick or Block Masonry</u>	299
<u>Section 520 Pipe Culverts</u>	301
<u>Section 521 Corrugated Steel Culverts</u>	307
<u>Section 522 Reinforced Concrete Culverts</u>	308
<u>Section 524 Salvaged Culverts</u>	309
<u>Section 525 Corrugated Aluminum Culverts</u>	310
<u>Section 526 Temporary Structures</u>	311
Revise 526.3.2(5) to clarify that loose materials including base aggregate are not allowed as the finished driving surface on the structure.	
<u>Section 527 Structural Plate Pipe and Pipe Arches</u>	313
<u>Section 530 Corrugated Plastic Pipe Culverts</u>	315
<u>Section 531 Ancillary Structure Foundations</u>	316
Revise 531.3.1 to add information for F four-chord truss structure span information and update example in Table 531-1.	
Revise 531.5 to add bid item range for foundation two-shaft butterfly (type) (structure) and revise number range for foundation single-shaft (type) (structure).	
<u>Section 532 Ancillary Superstructures</u>	319
Revise 532.5 to add bid item ranges. Move specific bid items for Butterfly 2-Chord and Butterfly 4-Chord to bid item list.	
<u>Section 550 Driven Piles</u>	325
Revise 550.2.1 to add requirement to provide copy of mill certification and edit formula to match SS-506.2 and AWS D1.5 Annex: Alternate Methods for Determining Preheats.	
Revise 550.3.4.1 to update reference information.	

## PART 600 Miscellaneous Construction

<u>Section 601 Concrete Curb and Gutter</u>	333
<u>Section 602 Concrete Sidewalks, Driveways, Loading Zones, Safety Islands, Surface Drains, Rumble Strips and Steps</u>	336
<u>Section 603 Concrete Barrier</u>	341
<u>Section 604 Slope Paving</u>	345
Add Table 604-01 for coarse aggregate material gradation requirements. This change was implemented via ASP-6 with the November 2023 letting.	
<u>Section 606 Riprap</u>	347
<u>Section 608 Storm Sewer</u>	349
<u>Section 611 Catch Basins, Manholes, and Inlets</u>	355
<u>Section 612 Underdrains</u>	358
Update 612.3.9 reference for coarse aggregate material gradation. This change was implemented via ASP-6 with the November 2023 letting.	
<u>Section 614 Semi-rigid Barrier Systems and End Treatments</u>	362
Revise 614.2.4 to replace damaged or missing EAT marker posts.	
Add Table 614-2 for fine aggregate gradation. This change was implemented via ASP-6 with the November 2023 letting.	
Add 614.3.1(1) to require final grading and associated earthwork before installing hardware.	
Revise 614.4 to add measurement information to "Replacing EAT Reflective Panel" and add information for "Replacing EAT marker post".	
Add bid item to 614.5 for "Replacing EAT Marker Posts" and add information to descriptions for replacing EAT reflective panel and replacing EAT marker post.	
<u>Section 615 Rustic Timber Items and Historical Markers</u>	370
<u>Section 616 Property and Right-of-Way Fence</u>	372
<u>Section 618 Maintenance and Repair of Haul Roads</u>	378
<u>Section 619 Mobilization</u>	379
<u>Section 620 Concrete Corrugated Median and Concrete Median Nose</u>	380

<u><a href="#">Section 621 Landmark Reference Monuments</a></u> .....	<a href="#">381</a>
<u><a href="#">Section 623 Dust Control Surface Treatment</a></u> .....	<a href="#">383</a>
<u><a href="#">Section 624 Water</a></u> .....	<a href="#">384</a>
<u><a href="#">Section 625 Topsoil and Salvaged Topsoil</a></u> .....	<a href="#">385</a>
<u><a href="#">Section 626 Peat Humus</a></u> .....	<a href="#">387</a>
<u><a href="#">Section 627 Mulching</a></u> .....	<a href="#">388</a>
<u><a href="#">Section 628 Erosion Control</a></u> .....	<a href="#">390</a>
Update 628.2.13(2) reference for coarse aggregate gradation. This change was implemented via ASP-6 with the November 2023 letting.	
<u><a href="#">Section 629 Fertilizer and Agricultural Limestone</a></u> .....	<a href="#">401</a>
<u><a href="#">Section 630 Seeding</a></u> .....	<a href="#">403</a>
Revise 630.3.5(1) seeding rates for seed mixtures 10, 20, 30 and 40.	
<u><a href="#">Section 631 Sodding</a></u> .....	<a href="#">409</a>
<u><a href="#">Section 632 Furnishing and Planting Plant Materials</a></u> .....	<a href="#">411</a>
<u><a href="#">Section 633 Delineators and Markers</a></u> .....	<a href="#">420</a>
<u><a href="#">Section 634 Wood and Tubular Steel Sign Posts</a></u> .....	<a href="#">423</a>
<u><a href="#">Section 635 Structural Steel Sign Supports</a></u> .....	<a href="#">425</a>
<u><a href="#">Section 637 Signing</a></u> .....	<a href="#">426</a>
<u><a href="#">Section 638 State Owned Signs and Supports</a></u> .....	<a href="#">433</a>
Revise 638.3.2(2) to include storing the signs during removal and moving.	
<u><a href="#">Section 639 Drilling Wells</a></u> .....	<a href="#">435</a>
Add reference to 639.2.1(2) for fine aggregate. This change was implemented via ASP-6 with the November 2023 letting.	
<u><a href="#">Section 642 Field Facilities</a></u> .....	<a href="#">440</a>
<u><a href="#">Section 643 Traffic Control</a></u> .....	<a href="#">443</a>
Revise name from "speed radar trailers" to "speed feedback trailers".	
Revise 643.2.3(6) to add bases and add crashworthy per MASH.	
Revise 643.2.4(2) to provide a completed portable changeable message sign Integration Request Form.	
Add 643.3.4 to minimize pavement damage and repair, as directed, following sign base removal for post mounted into concrete.	
Add 643.3.5(5) to not use PCMS in lieu of arrow board and change name from "cellular" to "traffic management center".	
Revise name from cellular to traffic management center (TMC) for bid item 643.1051 and from radar to feedback trailer for bid item 643.1500.	
<u><a href="#">Section 644 Temporary Pedestrian Facilities</a></u> .....	<a href="#">450</a>
<u><a href="#">Section 645 Geosynthetics</a></u> .....	<a href="#">452</a>
<u><a href="#">Section 646 Pavement Marking</a></u> .....	<a href="#">459</a>
Revise 646.2 to add time frame for pavement marking and glass bead certification submittals.	
Revise 646.3.1.1 to add that truck printouts are an acceptable option to replace DT2130 and DT2131 forms, add that on two-lane two-way roadways the lead vehicle may be removed, and add to distribute beads uniformly across the line.	
Revise 646.3.1.2(4) to remove the term exceeding and replace with a range for pounds per gallon of beads.	
Revise 646.3.1.3(1) to change from ambient or pavement temperature to ambient and pavement temperature for cold weather marking.	
Revise 646.3.1.5(2) to lower the yellow reflectivity readings for both paint and epoxy. Add paragraphs (5) and (6) to add language to support reflective width of a line.	
Revise 646.3.1.6.1(2) to add bead uniformity to the list of defined failures.	
Revise 646.3.2.3.1(1) to install grooves uniformly across the slot.	
Add subsection 646.3.2.3.3 for tape within grooving.	
Revise 646.3.3 to remove language regarding long lines at railroad crossings. This could be confusing since they are paid for separately.	
Revise 646.4(1) to add language about how railroad crossing should be paid.	
Revise 646.5.1 to add variable width for marking chevron bid items and clarify that preparing the surface is included with the marking bid items.	
<u><a href="#">Section 648 Locating No-passing Zones</a></u> .....	<a href="#">465</a>

<u><a href="#">Section 650 Construction Staking</a></u> .....	<b>467</b>
<u><a href="#">Section 651 General Requirements for Electrical Work</a></u> .....	<b>472</b>
<u><a href="#">Section 652 Electrical Conduit</a></u> .....	<b>474</b>
Update reference in 652.3.1.2(2) for coarse aggregate gradation. This change was implemented via ASP-6 with the November 2023 letting.	
<u><a href="#">Section 653 Pull Boxes and Junction Boxes</a></u> .....	<b>477</b>
<u><a href="#">Section 654 Bases</a></u> .....	<b>478</b>
<u><a href="#">Section 655 Electrical Wiring</a></u> .....	<b>479</b>
<u><a href="#">Section 656 Electrical Service</a></u> .....	<b>485</b>
<u><a href="#">Section 657 Poles, Arms, Standards, and Bases</a></u> .....	<b>488</b>
<u><a href="#">Section 658 Traffic Signals</a></u> .....	<b>492</b>
<u><a href="#">Section 659 Lighting</a></u> .....	<b>494</b>
<u><a href="#">Section 660 High Mast Lighting Lowering Assemblies</a></u> .....	<b>496</b>
<u><a href="#">Section 661 Temporary Traffic Signals and Temporary Ramp Meters</a></u> .....	<b>498</b>
<u><a href="#">Section 670 General Requirements for Intelligent Transportation Systems</a></u> .....	<b>504</b>
<u><a href="#">Section 671 Intelligent Transportation Systems - Conduit</a></u> .....	<b>506</b>
<u><a href="#">Section 673 Communication Vaults</a></u> .....	<b>508</b>
<u><a href="#">Section 674 Intelligent Transportation Systems - Cable</a></u> .....	<b>509</b>
<u><a href="#">Section 675 Controllers and Detectors</a></u> .....	<b>512</b>
<u><a href="#">Section 677 Cameras</a></u> .....	<b>514</b>
<u><a href="#">Section 678 Communication Systems</a></u> .....	<b>516</b>
<u><a href="#">Section 690 Sawing</a></u> .....	<b>519</b>

Revise 690.4(2) measurement language for sawing in conjunction with concrete pavement repair and replacement or concrete base patching.

## **PART 700 Quality Management Program**

<u><a href="#">Section 701 General QMP Requirements</a></u> .....	<b>521</b>
<u><a href="#">Section 710 General Concrete QMP</a></u> .....	<b>525</b>
<u><a href="#">Section 715 QMP Concrete Pavement, Cast-in-Place Barrier and Structures</a></u> .....	<b>530</b>
<u><a href="#">Section 716 QMP Ancillary Concrete</a></u> .....	<b>536</b>
<u><a href="#">Section 730 QMP Base Aggregate</a></u> .....	<b>538</b>
<u><a href="#">Section 740 QMP Ride</a></u> .....	<b>542</b>

## **Bid Items**

<b>100 Bid Items</b> .....	<b>547</b>
<b>200 Bid Items</b> .....	<b>547</b>
Add bid item 204.0167 for "Removing Cable Barrier".	
<b>300 Bid Items</b> .....	<b>548</b>
Add bid item 390.0100 "Removing Pavement for Base Patching" by the CY. Retire "Base Patching" by the SY. Retire "Base Patching Asphaltic" by SY. Add bid item 390.0305 "Base Patching Concrete HES" by the CY. Add bid item 390.0405 "Base Patching Concrete SHES" by the CY. Retire bid item "Base Patching Concrete SHES" by the SY. These changes were implemented via ASP-6 with the November 2023 letting.	
<b>400 Bid Items</b> .....	<b>550</b>
<b>500 Bid Items</b> .....	<b>552</b>
Add bid item 531.5030 for "Foundation Two-Shaft Butterfly Type B-I (structure)".	
Add bid item 532.5030 for "Butterfly 2-Chord Type I (structure)".	
<b>600 Bid Items</b> .....	<b>566</b>
Add bid items 611.0656 for "Inlet Covers Type VV-B" and 611.3260 for "Inlets 2x3.5-FT".	
Add bid item 614.0954 for "Replacing EAT Marker Posts".	
Rename bid item 643.1051 from "Traffic Control Signs PCMS with Cellular Communications" to "Traffic Control Signs PMCS with TMC communications".	
Rename bid item 643.1500 from "Traffic Control Speed Radar Trailer" to "Traffic Control Speed Feedback Trailer".	
Add bid items 646.7305 and 646.7320 for Marking Chevron Paint and Epoxy 12-inch.	

<u>700 Bid Items</u>	.....	<b>586</b>
----------------------	-------	------------

## **Appendix**

<u>Conversion Table U.S. Standard Measure to SI Metric</u>	.....	<b>587</b>
<u>Standard Sieve Sizes</u>	.....	<b>588</b>
<u>Bid Item Unit Abbreviations</u>	.....	<b>588</b>